

დანართები: 18-27

ქალაქ თბილისის მუნიციპალიტეტის მერიის
და რაიონული გამგეობების
ადმინისტრაციული შენობების
ენერგოაუდიტორული შეფასება



დაგენბახ ლენდსკეიპს

სარჩევი

დანართი 18: რესურსეფექტური საინჟინრო სისტემების გეგმური მომსახურების სამუშაოები 2	
დანართი 19: ქ. თბილისის მუნიციპალიტეტის მერიის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები.....	6
დანართი 20: გლდანის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	32
დანართი 21: ვაკის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	56
დანართი 22: დიდუბის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	80
დანართი 23: ნაძალადევის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	104
დანართი 24: მთაწმინდის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	128
დანართი 25: ჩუღურეთის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	152
დანართი 26: ისანის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	176
დანართი 27: სამგორის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები	200

დანართი 18: რესურსეფექტური საინჟინრო სისტემების გეგმური მომსახურების სამუშაოები

ასეთი პროტოკოლები შეიძლება შედგენილ იქნეს საინჟინრო სისტემებისათვის მას მერე, რაც ინსტალატორი კომპანია საგარანტიო პერიოდის გასვლის შემდგომ მომსახურების პაკეტს გადასცემს შესაბამის სამსახურს. გარდა ქვემოთ ჩამოთვლილის სისტემებისა მსგავსი პროტოკოლები შეიქმნება სხვა მოწყობილობა/დანადგარებისათვის.

ფოტოვოლტაური პანელელებით ელ.მომარაგების სისტემა

სისტემა / სისტემის ნაწილი	სამუშაოს აღწერილობა	შენიშვნა
ყოველდღიური		
სადენები და კაბელმზიდები	სადენების და კაბელმზიდების /ვიზუალური დათვალიერება, დაზიანების დაფიქსირება.	შესაძლებელია გაკეთდეს შიდა რესურსით
კვირაში ერთხელ		
თვეში ერთხელ		
	კვარტალში ერთხელ	
	სეზონურად ან 6 თვეში ერთხელ	
	წელიწადში ერთხელ	
	სხვა პერიოდულობით ან საჭიროების მიხედვით	

მზის თერმული კოლექტორები და ცხელი წყლით მომარაგების სისტემა

სისტემა / სისტემის ნაწილი	სამუშაოს აღწერილობა	შენიშვნა
ყოველდღიური		
კვირაში ერთხელ		
თვეში ერთხელ		
	კვარტალში ერთხელ	
	სეზონურად ან 6 თვეში ერთხელ	
	წელიწადში ერთხელ	
	სხვა პერიოდულობით ან საჭიროების მიხედვით	

თბური ტუმბო

სისტემა / სისტემის ნაწილი	სამუშაოს აღწერილობა	შენიშვნა
	ყოველდღიური	
	კვირაში ერთხელ	

	თვეში ერთხელ	
	კვარტალში ერთხელ	
	სეზონურად ან 6 თვეში ერთხელ	
	წელიწადში ერთხელ	
	სხვა პერიოდულობით ან საჭიროების მიხედვით	

შენობის მართვის და მონიტორინგის სისტემა

სისტემა / სისტემის ნაწილი	სამუშაოს აღწერილობა	შენიშვნა
ყოველდღიური		
კვირაში ერთხელ		
თვეში ერთხელ		
კვარტალში ერთხელ		
სეზონურად ან 6 თვეში ერთხელ		

	წელიწადში ერთხელ	
	სხვა პერიოდულობით ან საჭიროების მიხედვით	

დანართი 19: ქ. თბილისის მუნიციპალიტეტის მერიის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

აკრონიმები:

Plant Simulation Results - დანადგარის სიმულაციის შედეგები

Air System Simulation Results - საჰაერო სისტემის სიმულაციის შედეგები

Air System Information - ინფორმაცია საჰაერო სისტემის შესახებ

Size Calculation Information - ინფორმაცია ზომის კალკულაციის შესახებ

Cooling Coil Sizing Data - გამაგრილებელი კოჭის კალიბრირების მონაცემები

Heating Coil Sizing Data - გამათბობელი კოჭის კალიბრირების მონაცემები

Ventilation Fan Sizing Data - ვენტილატორის ზომის მონაცემები

Exhaust Fan Sizing Data- გამწოვი ვენტილატორის მონაცემები

Outdoor Ventilation Air Data - გარე ვენტილაციის საჰაერო მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	0	0
February	0	0	0	0	0	0
March	6227	6227	6227	1460	0	0
April	46628	46628	46628	10887	0	0
May	177124	177124	177124	41592	0	0
June	347698	347698	347698	83317	0	0
July	446182	446182	446182	109144	0	0
August	451111	451111	451111	110539	0	0
September	270842	270842	270842	64760	0	0
October	107390	107390	107390	25252	0	0
November	0	0	0	0	0	0
December	0	0	0	0	0	0
Total	1853200	1853200	1853200	446952	0	0

Air System Simulation Results (Table 1) :

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)	Ventilation Fan (kWh)	Exhaust Fan (kWh)	Terminal Fan (kWh)
January	0	16558	0	214634	826	826	0
February	0	15245	0	212345	746	746	0
March	45	0	6190	154864	826	826	0
April	314	0	46385	0	800	800	0
May	1455	0	175468	0	826	826	0
June	5114	0	342645	0	800	800	0
July	11000	0	435184	0	826	826	0
August	13309	0	437739	0	826	826	0
September	4267	0	266450	0	800	800	0
October	1102	0	106254	5701	826	826	0
November	0	7764	0	69534	800	800	0
December	0	13267	0	176034	826	826	0
Total	36607	52835	1816312	833111	9727	9727	0

Air System Simulation Results (Table 2) :

Month	Lighting (kWh)	Electric Equipment (kWh)
January	48751	48751
February	43120	43120
March	48270	48270
April	44997	44997
May	48751	48751
June	46393	46393
July	46874	46874
August	48751	48751
September	44517	44517
October	48751	48751
November	46874	46874
December	46393	46393
Total	562441	562441

Air System Information

Air System Name **As_build**

Air System Type **2P-FC**

Equipment Class **TERM**

Number of zones **31**
Floor Area **15014,0** m²

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **25,6** kW
Sensible coil load **23,6** kW
Coil L/s at Jul 1500 **1199** L/s
Max coil L/s **1199** L/s
Sensible heat ratio **0,923**
Water flow @ 6,0 K rise **1,02** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C
Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **36,9** kW
Coil L/s at Des Htg **1199** L/s
Max coil L/s **1199** L/s
Water flow @ 20,0 K drop **0,44** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1199** L/s
Standard L/s **1137** L/s
Actual max L/(s·m²) **0,08** L/(s·m²)

Fan motor BHP **1,40** BHP
Fan motor kW **1,11** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1199** L/s

Standard L/s **1137** L/s

Actual max L/(s·m?)	0,08 L/(s·m?)	Fan motor BHP	1,40 BHP
		Fan motor kW	1,11 kW
		Fan static	500 Pa

Outdoor Ventilation Air Data

Design airflow L/s	1199 L/s	L/s/person	0,80
L/(s·m?)	0,08 L/(s·m?)	L/s/person

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	4726 m?	555531	-	4726 m?	-	-
Wall Transmission	4539 m?	59723	-	4539 m?	164529	-
Roof Transmission	288 m?	4042	-	288 m?	3831	-
Window Transmission	4726 m?	234631	-	4726 m?	693322	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	600 m?	0	-	600 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	150140 W	127839	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	150140 W	140188	-	0	0	-
People	1508	88195	90602	0	0	0
Infiltration	-	61585	-977	-	165039	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	5%	51336	0
>> Total Zone Loads	-	1271732	89625	-	1078057	0
Zone Conditioning	-	1237456	89625	-	1040245	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Ventilation Load	1199 L/s	10982	1791	1199 L/s	35407	0
Ventilation Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	1250658	91417	-	1073431	0
Cooling Coil	-	19772	1957	-	0	0
Heating Coil	-	0	-	-	36906	-
Terminal Unit Cooling	-	1230886	88566	-	0	0
Terminal Unit Heating	-	0	-	-	1036542	-

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_as_build

05.15.2017

09:59

>> Total Conditioning	-	1250658	90523	-	1073448	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	0	0
February	0	0	0	0	0	0
March	11908	11908	11908	2766	0	0
April	85542	85542	85477	20101	0	0
May	213162	213162	213115	50080	0	0
June	334352	334352	334352	79886	0	0
July	389367	389367	389367	95223	0	0
August	394936	394936	394936	96890	0	0
September	265905	265905	265905	63359	0	0
October	150640	150640	150640	35106	0	0
November	0	0	0	0	0	0
December	0	0	0	0	0	0
Total	1845811	1845811	1845699	443410	0	0

Air System Simulation Results (Table 1) :

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)	Ventilation Fan (kWh)	Exhaust Fan (kWh)	Terminal Fan (kWh)
January	0	16558	0	31955	826	826	0
February	0	15245	0	44719	746	746	0
March	45	0	11863	18790	826	826	0
April	314	0	85227	0	800	800	0
May	1455	0	211707	0	826	826	0
June	5114	0	329238	0	800	800	0
July	11000	0	378367	0	826	826	0
August	13309	0	381627	0	826	826	0
September	4267	0	261638	0	800	800	0
October	1102	0	149537	732	826	826	0
November	0	7764	0	2863	800	800	0
December	0	13267	0	24344	826	826	0
Total	36607	52835	1809204	123404	9727	9727	0

Air System Simulation Results (Table 2) :

Month	Lighting (kWh)	Electric Equipment (kWh)
January	48751	48751
February	43120	43120
March	48270	48270
April	44997	44997
May	48751	48751
June	46393	46393
July	46874	46874
August	48751	48751
September	44517	44517
October	48751	48751
November	46874	46874
December	46393	46393
Total	562441	562441

Air System Information

Air System Name **As_build**

Equipment Class **TERM**

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_as_build

05.15.2017

09:59

Air System Type **2P-FC**

Number of zones **31**

Floor Area **15014,0** m²

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **25,6** kW

Load occurs at **Jul 1500**

Sensible coil load **23,6** kW

OA DB / WB **34,4 / 21,8** °C

Coil L/s at Jul 1500 **1199** L/s

Entering DB / WB **34,4 / 21,8** °C

Max coil L/s **1199** L/s

Leaving DB / WB **17,2 / 16,0** °C

Sensible heat ratio **0,923**

Bypass Factor **0,100**

Water flow @ 6,0 K rise **1,02** L/s

Heating Coil Sizing Data

Max coil load **36,9** kW

Load occurs at **Des Htg**

Coil L/s at Des Htg **1199** L/s

Ent. DB / Lvg DB **-5,7 / 21,2** °C

Max coil L/s **1199** L/s

Water flow @ 20,0 K drop **0,44** L/s

Ventilation Fan Sizing Data

Actual max L/s **1199** L/s

Fan motor BHP **1,40** BHP

Standard L/s **1137** L/s

Fan motor kW **1,11** kW

Actual max L/(s·m²) **0,08** L/(s·m²)

Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1199** L/s

Actual max L/(s·m²) **0,08** L/(s·m²)

Standard L/s **1137** L/s

Fan motor BHP **1,40** BHP Fan static **500** Pa
Fan motor kW **1,11** kW

Outdoor Ventilation Air Data

Design airflow L/s **1199** L/s L/s/person **0,80**
L/(s·m?) **0,08** L/(s·m?) L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_as_built

05.15.2017

01:54

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	4726 m²	462421	-	4726 m²	-	-
Wall Transmission	4539 m²	59723	-	4539 m²	164538	-
Roof Transmission	288 m²	4041	-	288 m²	3831	-
Window Transmission	4726 m²	52590	-	4726 m²	155400	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	600 m²	0	-	600 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	150140 W	127839	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	150140 W	140188	-	0	0	-
People	1508	88195	90602	0	0	0
Infiltration	-	61585	20823	-	165039	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	5%	24440	0
>> Total Zone Loads	-	996580	111425	-	513249	0
Zone Conditioning	-	969330	111425	-	506393	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Ventilation Load	1199 L/s	11126	2674	1199 L/s	35933	0
Ventilation Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	982677	114098	-	540105	0
Cooling Coil	-	19772	1957	-	0	0
Heating Coil	-	0	-	-	36906	-
Terminal Unit Cooling	-	962905	112488	-	0	0
Terminal Unit Heating	-	0	-	-	503184	-
>> Total Conditioning	-	982677	114445	-	540091	0

Key:	Positive values are cig loads Negative values are htg loads	Positive values are htg loads Negative values are cig loads
-------------	--	--

Air System Simulation Results (Table 1) :

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)	Ventilation Fan (kWh)	Exhaust Fan (kWh)	Terminal Fan (kWh)
January	0	16558	0	170826	826	826	0
February	0	15245	0	170204	746	746	0
March	45	0	7281	119606	826	826	0
April	314	0	53113	0	800	800	0
May	1455	0	180441	0	826	826	0
June	5114	0	335418	0	800	800	0
July	11000	0	417334	0	826	826	0
August	13309	0	419882	0	826	826	0
September	4267	0	261296	0	800	800	0
October	1102	0	114339	4582	826	826	0
November	0	7764	0	51836	800	800	0
December	0	13267	0	140410	826	826	0
Total	36607	52835	1789105	657462	9727	9727	0

Air System Simulation Results (Table 2) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_as_build

05.15.2017

01:54

Month	Lighting (kWh)	Electric Equipment (kWh)
January	48751	48751
February	43120	43120
March	48270	48270
April	44997	44997
May	48751	48751
June	46393	46393
July	46874	46874
August	48751	48751
September	44517	44517
October	48751	48751
November	46874	46874
December	46393	46393
Total	562441	562441

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **31**
 Floor Area **15014,0** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **25,6** kW
 Sensible coil load **23,6** kW
 Coil L/s at Jul 1500 **1199** L/s
 Max coil L/s **1199** L/s
 Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **1,02** L/s

Load occurs at **Jul 1500**
 OA DB / WB **34,4 / 21,8** °C
 Entering DB / WB **34,4 / 21,8** °C
 Leaving DB / WB **17,2 / 16,0** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load	36,9 kW	Load occurs at	Des Htg
Coil L/s at Des Htg	1199 L/s	Ent. DB / Lvg DB	-5,7 / 21,2 °C
Max coil L/s	1199 L/s		
Water flow @ 20,0 K drop	0,44 L/s		

Ventilation Fan Sizing Data

Actual max L/s	1199 L/s	Fan motor BHP	1,40 BHP
Standard L/s	1137 L/s	Fan motor kW	1,11 kW
Actual max L/(s·m?)	0,08 L/(s·m?)	Fan static	500 Pa

Exhaust Fan Sizing Data

Actual max L/s	1199 L/s	Fan motor BHP	1,40 BHP
Standard L/s	1137 L/s	Fan motor kW	1,11 kW
Actual max L/(s·m?)	0,08 L/(s·m?)	Fan static	500 Pa

Outdoor Ventilation Air Data

Design airflow L/s	1199 L/s	L/s/person	0,80
L/(s·m?)	0,08 L/(s·m?)	L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_as_build

05.15.2017

02:14

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	4726 m²	541971	-	4726 m²	-	-
Wall Transmission	4539 m²	12766	-	4539 m²	32368	-
Roof Transmission	288 m²	3981	-	288 m²	3831	-
Window Transmission	4726 m²	249859	-	4726 m²	693322	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	600 m²	0	-	600 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	150140 W	127839	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	150140 W	140188	-	0	0	-
People	1508	88195	90602	0	0	0
Infiltration	-	65191	3162	-	165039	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	5%	44728	0
>> Total Zone Loads	-	1229989	93764	-	939288	0
Zone Conditioning	-	1207351	93764	-	929094	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Ventilation Load	1199 L/s	11761	1886	1199 L/s	35843	0
Ventilation Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	1221333	95650	-	962716	0
Cooling Coil	-	20535	1403	-	0	0
Heating Coil	-	0	-	-	36906	-
Terminal Unit Cooling	-	1200798	93318	-	0	0
Terminal Unit Heating	-	0	-	-	925805	-
>> Total Conditioning	-	1221333	94720	-	962711	0

Key:	Positive values are clg loads Negative values are htg loads	Positive values are htg loads Negative values are clg loads
-------------	--	--

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	0	0
February	0	0	0	0	0	0
March	7817	7817	7817	1820	0	0
April	57317	57317	57317	13342	0	0
May	193667	193667	193667	45434	0	0
June	361106	361106	361106	86515	0	0
July	452723	452723	452723	110835	0	0
August	455956	455956	455956	111838	0	0
September	280759	280759	280759	67117	0	0
October	121388	121388	121388	28477	0	0
November	0	0	0	0	0	0
December	0	0	0	0	0	0
Total	1930732	1930732	1930732	465379	0	0

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_as_build

05.15.2017

02:14

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)	Ventilation Fan (kWh)	Exhaust Fan (kWh)	Terminal Fan (kWh)
January	0	16558	0	169896	826	826	0
February	0	15245	0	169386	746	746	0
March	45	0	7280	118987	826	826	0
April	314	0	53103	0	800	800	0
May	1455	0	180201	0	826	826	0
June	5114	0	334812	0	800	800	0
July	11000	0	416523	0	826	826	0
August	13309	0	419149	0	826	826	0
September	4267	0	260963	0	800	800	0
October	1102	0	114416	4562	826	826	0
November	0	7764	0	51421	800	800	0
December	0	13267	0	139605	826	826	0
Total	36607	52835	1786447	653857	9727	9727	0

Air System Simulation Results (Table 2) :

Month	Lighting (kWh)	Electric Equipment (kWh)
January	48751	48751
February	43120	43120
March	48270	48270
April	44997	44997
May	48751	48751
June	46393	46393
July	46874	46874
August	48751	48751
September	44517	44517
October	48751	48751
November	46874	46874
December	46393	46393
Total	562441	562441

Air System Information

Air System Name **As_build**

Air System Type **2P-FC**

Equipment Class **TERM**

Number of zones **31**
 Floor Area **15014,0** m²

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **25,6** kW
 Sensible coil load **23,6** kW
 Coil L/s at Jul 1500 **1199** L/s
 Max coil L/s **1199** L/s
 Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **1,02** L/s

Load occurs at **Jul 1500**
 OA DB / WB **34,4 / 21,8** °C
 Entering DB / WB **34,4 / 21,8** °C
 Leaving DB / WB **17,2 / 16,0** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **36,9** kW
 Coil L/s at Des Htg **1199** L/s
 Max coil L/s **1199** L/s
 Water flow @ 20,0 K drop **0,44** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1199** L/s
 Standard L/s **1137** L/s
 Actual max L/(s·m²) **0,08** L/(s·m²)

Fan motor BHP **1,40** BHP
 Fan motor kW **1,11** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1199** L/s

Standard L/s **1137** L/s

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_as_build

05.15.2017

02:14

Actual max L/(s·m?)	0,08	L/(s·m?)	Fan motor BHP	1,40	BHP
			Fan motor kW	1,11	kW
			Fan static	500	Pa

Outdoor Ventilation Air Data

Design airflow L/s	1199	L/s	L/s/person	0,80	L/s/person
L/(s·m?)	0,08	L/(s·m?)			

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	4726 m²	541971	-	4726 m²	-	-
Wall Transmission	4539 m²	12766	-	4539 m²	32368	-
Roof Transmission	288 m²	1264	-	288 m²	1478	-
Window Transmission	4726 m²	249859	-	4726 m²	693322	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	600 m²	0	-	600 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	150140 W	127839	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	150140 W	140188	-	0	0	-
People	1508	88195	90602	0	0	0
Infiltration	-	65191	3145	-	165039	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	5%	44610	0
>> Total Zone Loads	-	1227272	93747	-	936817	0
Zone Conditioning	-	1204531	93747	-	926888	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Ventilation Load	1199 L/s	11761	1886	1199 L/s	35843	0
Ventilation Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	1218513	95633	-	960510	0
Cooling Coil	-	20535	1403	-	0	0
Heating Coil	-	0	-	-	36906	-
Terminal Unit Cooling	-	1197978	93305	-	0	0
Terminal Unit Heating	-	0	-	-	923599	-

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_rebuilt

05.15.2017

03:18

>> Total Conditioning	-	1218513	94707	-	960505	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	0	0
February	0	0	0	0	0	0
March	6910	6910	6910	1617	0	0
April	51751	51751	51751	12068	0	0
May	190049	190049	190049	44604	0	0
June	368687	368687	368687	88305	0	0
July	470603	470603	470603	115076	0	0
August	473912	473912	473912	116111	0	0
September	286098	286098	286098	68397	0	0
October	114046	114046	114046	26809	0	0
November	0	0	0	0	0	0
December	0	0	0	0	0	0
Total	1962057	1962057	1962057	472985	0	0

Air System Simulation Results (Table 1) :

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)	Ventilation Fan (kWh)	Exhaust Fan (kWh)	Terminal Fan (kWh)
January	0	6534	0	214619	826	826	0
February	0	6300	0	212346	746	746	0
March	45	0	6331	147485	826	826	0
April	311	0	47667	0	800	800	0
May	1395	0	176784	0	826	826	0
June	4745	0	342957	0	800	800	0
July	10064	0	435259	0	826	826	0
August	12260	0	437864	0	826	826	0
September	4029	0	266579	0	800	800	0
October	1098	0	107179	4975	826	826	0
November	0	2402	0	69339	800	800	0
December	0	5075	0	176138	826	826	0
Total	33948	20312	1820619	824901	9727	9727	0

Air System Simulation Results (Table 2) :

Month	Vent. Reclaim Device (kWh)	Lighting (kWh)	Electric Equipment (kWh)
January	0	48751	48751
February	0	43120	43120
March	0	48270	48270
April	0	44997	44997
May	0	48751	48751
June	0	46393	46393
July	0	46874	46874
August	0	48751	48751
September	0	44517	44517
October	0	48751	48751
November	0	46874	46874
December	0	46393	46393
Total	0	562441	562441

Plant Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: CITY-HALL_rebuilt

05.15.2017

03:18

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	0	0
February	0	0	0	0	0	0
March	7183	7183	7183	1678	0	0
April	54259	54259	54259	12642	0	0
May	192997	192997	192997	45278	0	0
June	368440	368440	368440	88223	0	0
July	466609	466609	466609	114079	0	0
August	469759	469759	469759	115061	0	0
September	286223	286223	286223	68413	0	0
October	117347	117347	117347	27562	0	0
November	0	0	0	0	0	0
December	0	0	0	0	0	0
Total	1962817	1962817	1962817	472935	0	0

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	0	0
February	0	0	0	0	0	0
March	17109	17109	16790	4065	0	0
April	107262	107262	103317	25003	0	0
May	225059	225059	223336	52856	0	0
June	327986	327986	327817	78484	0	0
July	369033	369033	369033	90450	0	0
August	374114	374114	374114	92047	0	0
September	261302	261302	261302	62234	0	0
October	166510	166510	166510	38804	0	0
November	0	0	0	0	0	0
December	0	0	0	0	0	0
Total	1848375	1848375	1842220	443942	0	0

Air System Simulation Results (Table 1) :

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)	Ventilation Fan (kWh)	Exhaust Fan (kWh)	Terminal Fan (kWh)
January	0	1975	0	3448	826	826	0
February	0	2482	0	10287	746	746	0
March	45	0	19078	82	826	826	0
April	312	0	117556	0	800	800	0
May	1399	0	242290	0	826	826	0
June	4751	0	346746	0	800	800	0
July	10072	0	382394	0	826	826	0
August	12266	0	383301	0	826	826	0
September	4035	0	274801	0	800	800	0
October	1099	0	177639	28	826	826	0
November	0	217	0	3	800	800	0
December	0	1228	0	1413	826	826	0
Total	33978	5902	1943806	15262	9727	9727	0

Air System Simulation Results (Table 2) :

Month	Vent. Reclaim Device (kWh)	Lighting (kWh)	Electric Equipment (kWh)
January	0	48751	48751
February	0	43120	43120
March	0	48270	48270
April	0	44997	44997
May	0	48751	48751
June	0	46393	46393
July	0	46874	46874
August	0	48751	48751
September	0	44517	44517
October	0	48751	48751
November	0	46874	46874
December	0	46393	46393
Total	0	562441	562441

Air System Information

Air System Name **As_build**

Equipment Class **TERM**

Actual max L/(s·m?)	0,08 L/(s·m?)	Fan motor BHP	1,40 BHP
		Fan motor kW	1,11 kW
		Fan static	500 Pa

Outdoor Ventilation Air Data

Design airflow L/s	1199 L/s	L/s/person	0,80
L/(s·m?)	0,08 L/(s·m?)	L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_as_build

05.18.2017

Prepared by:

12:09

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	4726 m²	520447	-	4726 m²	-	-
Wall Transmission	4539 m²	12277	-	4539 m²	32368	-
Roof Transmission	288 m²	1286	-	288 m²	1478	-
Window Transmission	4726 m²	52590	-	4726 m²	155400	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	600 m²	0	-	600 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	150140 W	127839	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	150140 W	140188	-	0	0	-
People	1508	88195	90602	0	0	0
Infiltration	-	61585	20992	-	165039	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	5%	17714	0
>> Total Zone Loads	-	1004405	111594	-	371999	0
Zone Conditioning	-	977511	111594	-	364687	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Ventilation Load	1199 L/s	5497	1930	1199 L/s	18071	0
Ventilation Fan Load	1199 L/s	1110	-	1199 L/s	-1110	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	985229	113524	-	380538	0
Cooling Coil	-	14275	920	-	0	0
Heating Coil	-	0	-	-	18835	-
Terminal Unit Cooling	-	970954	113288	-	0	0

Terminal Unit Heating	-	0	-	-	361752	-
>> Total Conditioning	-	985229	114208	-	380586	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

დანართი 20: გლდანის რაიონის გამგეობის შენობის
ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1270	1270	1270	294	n/a	n/a
April	9337	9337	9337	2168	n/a	n/a
May	26864	26864	26864	6285	n/a	n/a
June	44179	44179	44179	10557	n/a	n/a
July	53582	53582	53582	13059	n/a	n/a
August	51834	51834	51834	12659	n/a	n/a
September	33089	33089	33089	7907	n/a	n/a
October	15612	15612	15612	3662	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	235768	235768	235768	56590	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_as_build

05.18.2017

Prepared by:

12:09

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9203	0	7072
February	0	8474	0	7547
March	25	0	1245	6935
April	175	0	9162	0
May	809	0	26055	0
June	2843	0	41337	0
July	6114	0	47467	0
August	7398	0	44437	0
September	2372	0	30718	0
October	613	0	14999	348
November	0	4316	0	1409
December	0	7374	0	6178
Total	20347	29367	215421	29488

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1377,6** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **14,2** kW

Sensible heat ratio **0,923**

Sensible coil load **13,1** kW

Water flow @ 6,0 K rise **0,57** L/s

Coil L/s at Jul 1500 **667** L/s

Max coil L/s **667** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,5** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 20,0 K drop **0,25** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
Fan motor kW **0,62** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
Fan motor kW **0,62** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58**
..... L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_new_windows

05.18.2017

Prepared by:

12:12

		DESIGN COOLING			DESIGN HEATING		
		COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
		COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)	
Window & Skylight Solar Loads	503 m?	85954	-	503 m?	-	-	
Wall Transmission	369 m?	4893	-	369 m?	13009	-	
Roof Transmission	500 m?	7016	-	500 m?	6651	-	
Window Transmission	503 m?	14202	-	503 m?	41845	-	
Skylight Transmission	0 m?	0	-	0 m?	0	-	
Door Loads	0 m?	0	-	0 m?	0	-	
Floor Transmission	791 m?	0	-	791 m?	0	-	
Partitions	0 m?	0	-	0 m?	0	-	
Ceiling	0 m?	0	-	0 m?	0	-	
Overhead Lighting	13776 W	11730	-	0	0	-	
Task Lighting	0 W	0	-	0	0	-	
Electric Equipment	13776 W	12863	-	0	0	-	
People	101	5925	6087	0	0	0	
Infiltration	-	0	0	-	0	0	
Miscellaneous	-	0	0	-	0	0	
Safety Factor	10% / 10%	14258	609	10%	6151	0	
>> Total Zone Loads	-	156841	6696	-	67656	0	
Zone Conditioning	-	150850	6696	-	68122	0	
Plenum Wall Load	0%	0	-	0	0	-	
Plenum Roof Load	0%	0	-	0	0	-	
Plenum Lighting Load	0%	0	-	0	0	-	
Exhaust Fan Load	667 L/s	617	-	667 L/s	-617	-	
Ventilation Load	667 L/s	5995	2260	667 L/s	20278	0	
Ventilation Fan Load	667 L/s	617	-	667 L/s	-617	-	
Space Fan Coil Fans	-	0	-	-	0	-	
Duct Heat Gain / Loss	0%	0	-	0%	0	-	
>> Total System Loads	-	158079	8955	-	87166	0	
Cooling Coil	-	10990	1088	-	0	0	
Heating Coil	-	0	-	-	20513	-	
Terminal Unit Cooling	-	147090	8043	-	0	0	

Terminal Unit Heating	-	0	-	-	66659	-
>> Total Conditioning	-	158079	9131	-	87172	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1107	1107	1107	257	n/a	n/a
April	7848	7848	7848	1825	n/a	n/a
May	20900	20900	20900	4890	n/a	n/a
June	33308	33308	33308	7956	n/a	n/a
July	40250	40250	40250	9807	n/a	n/a
August	39776	39776	39776	9709	n/a	n/a
September	25433	25433	25433	6072	n/a	n/a
October	13204	13204	13204	3084	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	181826	181826	181826	43600	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_new_windows

05.18.2017

Prepared by:

12:12

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9203	0	1962
February	0	8474	0	2633
March	25	0	1082	3825
April	175	0	7673	0
May	809	0	20091	0
June	2843	0	30466	0
July	6114	0	34135	0
August	7398	0	32379	0
September	2372	0	23061	0
October	613	0	12591	190
November	0	4316	0	259
December	0	7374	0	1751
Total	20347	29367	161479	10619

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1377,6** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **14,2** kW

Sensible heat ratio **0,923**

Sensible coil load **13,1** kW

Water flow @ 6,0 K rise **0,57** L/s

Coil L/s at Jul 1500 **667** L/s

Max coil L/s **667** L/s

Load occurs at **Jul 1500**
 OA DB / WB **34,4 / 21,8** °C
 Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,5** kW
 Coil L/s at Des Htg **667** L/s
 Max coil L/s **667** L/s
 Water flow @ 20,0 K drop **0,25** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
 L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58**
 L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_walls_insulation

05.18.2017

Prepared by:

12:15

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m?	53323	-	503 m?	-	-
Wall Transmission	369 m?	4893	-	369 m?	13009	-
Roof Transmission	500 m?	7016	-	500 m?	6651	-
Window Transmission	503 m?	5704	-	503 m?	16805	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	791 m?	0	-	791 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13776 W	11730	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12863	-	0	0	-
People	101	5925	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	10145	609	10%	3647	0
>> Total Zone Loads	-	111598	6696	-	40112	0
Zone Conditioning	-	106928	6696	-	39588	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	617	-	667 L/s	-617	-
Ventilation Load	667 L/s	6036	2214	667 L/s	20240	0
Ventilation Fan Load	667 L/s	617	-	667 L/s	-617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	114199	8909	-	58593	0
Cooling Coil	-	10990	1088	-	0	0
Heating Coil	-	0	-	-	20513	-
Terminal Unit Cooling	-	103209	7834	-	0	0

Terminal Unit Heating	-	0	-	-	38086	-
>> Total Conditioning	-	114199	8922	-	58600	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1411	1411	1411	327	n/a	n/a
April	10175	10175	10175	2364	n/a	n/a
May	27440	27440	27440	6419	n/a	n/a
June	43550	43550	43550	10407	n/a	n/a
July	52084	52084	52084	12703	n/a	n/a
August	50257	50257	50257	12284	n/a	n/a
September	32602	32602	32602	7790	n/a	n/a
October	16328	16328	16328	3823	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	233847	233847	233847	56117	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_walls_insulation

05.18.2017

Prepared by:

12:15

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9203	0	4122
February	0	8474	0	4799
March	25	0	1387	4705
April	175	0	10000	0
May	809	0	26632	0
June	2843	0	40708	0
July	6114	0	45970	0
August	7398	0	42859	0
September	2372	0	30230	0
October	613	0	15715	242
November	0	4316	0	624
December	0	7374	0	3656
Total	20347	29367	213500	18147

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1377,6** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **14,2** kW

Water flow @ 6,0 K rise **0,57** L/s

Sensible coil load **13,1** kW

Coil L/s at Jul 1500 **667** L/s

Max coil L/s **667** L/s

Sensible heat ratio **0,923**

Load occurs at **Jul 1500**
 OA DB / WB **34,4 / 21,8** °C
 Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,5** kW
 Coil L/s at Des Htg **667** L/s
 Max coil L/s **667** L/s
 Water flow @ 20,0 K drop **0,25** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
 L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58**
 L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_walls&roof_insulation

05.18.2017

Prepared by:

12:18

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	85954	-	503 m²	-	-
Wall Transmission	369 m²	982	-	369 m²	2560	-
Roof Transmission	500 m²	7016	-	500 m²	6651	-
Window Transmission	503 m²	14202	-	503 m²	41845	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11730	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12863	-	0	0	-
People	101	5925	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	13867	609	10%	5106	0
>> Total Zone Loads	-	152540	6696	-	56162	0
Zone Conditioning	-	147822	6696	-	55887	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	617	-	667 L/s	-617	-
Ventilation Load	667 L/s	6059	2443	667 L/s	20272	0
Ventilation Fan Load	667 L/s	617	-	667 L/s	-617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	155116	9139	-	74925	0
Cooling Coil	-	10990	1088	-	0	0
Heating Coil	-	0	-	-	20513	-
Terminal Unit Cooling	-	144126	8215	-	0	0

Terminal Unit Heating	-	0	-	-	54403	-
>> Total Conditioning	-	155116	9302	-	74917	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1448	1448	1448	336	n/a	n/a
April	10286	10286	10286	2391	n/a	n/a
May	27104	27104	27104	6340	n/a	n/a
June	42503	42503	42503	10156	n/a	n/a
July	50628	50628	50628	12350	n/a	n/a
August	48972	48972	48972	11972	n/a	n/a
September	32036	32036	32036	7653	n/a	n/a
October	16549	16549	16549	3871	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	229527	229527	229527	55068	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_walls&roof_insulation

05.18.2017

Prepared by:

12:18

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9203	0	2846
February	0	8474	0	3693
March	25	0	1423	3916
April	175	0	10112	0
May	809	0	26296	0
June	2843	0	39660	0
July	6114	0	44514	0
August	7398	0	41575	0
September	2372	0	29664	0
October	613	0	15936	200
November	0	4316	0	311
December	0	7374	0	2533
Total	20347	29367	209179	13498

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1377,6** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **14,2** kW

Water flow @ 6,0 K rise **0,57** L/s

Sensible coil load **13,1** kW

Coil L/s at Jul 1500 **667** L/s

Max coil L/s **667** L/s

Sensible heat ratio **0,923**

Load occurs at **Jul 1500**
 OA DB / WB **34,4 / 21,8** °C
 Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,5** kW
 Coil L/s at Des Htg **667** L/s
 Max coil L/s **667** L/s
 Water flow @ 20,0 K drop **0,25** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
 L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58**
 L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_rebuild

05.18.2017

Prepared by:

02:32

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	85954	-	503 m²	-	-
Wall Transmission	369 m²	982	-	369 m²	2560	-
Roof Transmission	500 m²	2232	-	500 m²	2566	-
Window Transmission	503 m²	14202	-	503 m²	41845	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11730	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12863	-	0	0	-
People	101	5925	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	13389	609	10%	4697	0
>> Total Zone Loads	-	147277	6696	-	51668	0
Zone Conditioning	-	143386	6696	-	51407	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	617	-	667 L/s	-617	-
Ventilation Load	667 L/s	6080	2511	667 L/s	20270	0
Ventilation Fan Load	667 L/s	617	-	667 L/s	-617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	150700	9206	-	70443	0
Cooling Coil	-	10990	1088	-	0	0
Heating Coil	-	0	-	-	20513	-
Terminal Unit Cooling	-	139710	8376	-	0	0

Terminal Unit Heating	-	0	-	-	49922	-
>> Total Conditioning	-	150700	9464	-	70435	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)
January	0	0	0	0
February	0	0	0	0
March	1830	1830	1792	432
April	11126	11126	10836	2610
May	22526	22526	22450	5297
June	31784	31784	31775	7594
July	36817	36817	36817	8973
August	36415	36415	36415	8892
September	24382	24382	24382	5814
October	15372	15372	15372	3582
November	0	0	0	0
December	0	0	0	0
Total	180252	180252	179839	43193

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_rebuild

05.18.2017

Prepared by:

02:32

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	1894	0	35
February	0	1911	0	112
March	25	0	1805	12
April	174	0	10952	0
May	777	0	21749	0
June	2637	0	29146	0
July	5590	0	31227	0
August	6805	0	29610	0
September	2237	0	22145	0
October	611	0	14762	2
November	0	249	0	0
December	0	1221	0	24
Total	18856	5276	161396	184

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1377,6** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **9,4** kW

Sensible heat ratio **0,929**

Sensible coil load **8,8** kW

Water flow @ 6,0 K rise **0,38** L/s

Coil L/s at Jun 1500 **667** L/s

Max coil L/s **667** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **10,4** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 20,0 K drop **0,12** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,6 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
Fan motor kW **0,62** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
Fan motor kW **0,62** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58**
..... L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_vent_reclaim

05.18.2017

Prepared by:

02:29

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	53323	-	503 m²	-	-
Wall Transmission	369 m²	982	-	369 m²	2560	-
Roof Transmission	500 m²	2232	-	500 m²	2566	-
Window Transmission	503 m²	5704	-	503 m²	16805	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11730	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12863	-	0	0	-
People	101	5925	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	9276	609	10%	2193	0
>> Total Zone Loads	-	102034	6696	-	24125	0
Zone Conditioning	-	98570	6696	-	24583	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	617	-	667 L/s	-617	-
Ventilation Load	667 L/s	3028	2301	667 L/s	10144	0
Ventilation Fan Load	667 L/s	617	-	667 L/s	-617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	102833	8996	-	33492	0
Cooling Coil	-	7962	517	-	0	0
Heating Coil	-	0	-	-	10370	-
Terminal Unit Cooling	-	94871	8510	-	0	0

Terminal Unit Heating	-	0	-	-	23122	-
>> Total Conditioning	-	102833	9026	-	33492	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1496	1496	1496	347	n/a	n/a
April	10545	10545	10545	2451	n/a	n/a
May	27786	27786	27786	6498	n/a	n/a
June	44191	44191	44191	10553	n/a	n/a
July	53090	53090	53090	12932	n/a	n/a
August	51307	51307	51307	12524	n/a	n/a
September	33052	33052	33052	7894	n/a	n/a
October	16292	16292	16292	3814	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	237759	237759	237759	57013	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Gldani_vent_reclaim

05.18.2017

Prepared by:

02:29

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	3106	0	7075
February	0	2776	0	7528
March	25	0	1471	3863
April	173	0	10372	0
May	776	0	27010	0
June	2636	0	41555	0
July	5590	0	47500	0
August	6803	0	44504	0
September	2235	0	30817	0
October	610	0	15682	88
November	0	1064	0	1341
December	0	2261	0	6095
Total	18848	9207	218911	25990

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1377,6** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **9,5** kW

Water flow @ 6,0 K rise **0,38** L/s

Sensible coil load **8,8** kW

Coil L/s at Jun 1500 **667** L/s

Max coil L/s **667** L/s

Sensible heat ratio **0,929**

Load occurs at **Jun 1500**
 OA DB / WB **33,8 / 21,8** °C
 Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **10,4** kW
 Coil L/s at Des Htg **667** L/s
 Max coil L/s **667** L/s
 Water flow @ 20,0 K drop **0,12** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **7,6 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **667** L/s
 Standard L/s **632** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,78** BHP
 Fan motor kW **0,62** kW
 Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
 L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58**
 L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for Vake

Project Name: Vake_as_built

05.19.2017

Prepared by:

07:31

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m?	85954	-	503 m?	-	-
Wall Transmission	369 m?	4893	-	369 m?	13009	-
Roof Transmission	500 m?	7016	-	500 m?	6651	-
Window Transmission	503 m?	14202	-	503 m?	41845	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	791 m?	0	-	791 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13776 W	11730	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12863	-	0	0	-
People	101	5925	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	14258	609	10%	6151	0
>> Total Zone Loads	-	156841	6696	-	67656	0
Zone Conditioning	-	150850	6696	-	68122	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	617	-	667 L/s	-617	-
Ventilation Load	667 L/s	2997	2256	667 L/s	10139	0
Ventilation Fan Load	667 L/s	617	-	667 L/s	-617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	155082	8951	-	77027	0
Cooling Coil	-	7992	522	-	0	0
Heating Coil	-	0	-	-	10375	-
Terminal Unit Cooling	-	147090	8607	-	0	0

Terminal Unit Heating	-	0	-	-	66659	-
>> Total Conditioning	-	155082	9129	-	77033	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

დანართი 21: ვაკის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	617	617	617	142	n/a	n/a
March	1311	1311	1311	304	n/a	n/a
April	9608	9608	9608	2235	n/a	n/a
May	26573	26573	26573	6217	n/a	n/a
June	44997	44997	44997	10731	n/a	n/a
July	52542	52542	52542	12814	n/a	n/a
August	52370	52370	52370	12805	n/a	n/a
September	33926	33926	33926	8078	n/a	n/a
October	16073	16073	16073	3753	n/a	n/a
November	3501	3501	3501	813	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	241518	241518	241518	57892	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **18,0 / 16,8** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,1** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 11,1 K drop **0,46** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 22,0** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,00** BHP
Fan motor kW **0,00** kW
Fan static **0** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for Vake

Project Name: Vake_new_windows

05.19.2017

Prepared by:

07:40

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,5 °C / 21,7 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	68891	-	503 m²	-	-
Wall Transmission	369 m²	4855	-	369 m²	13009	-
Roof Transmission	500 m²	6389	-	500 m²	6651	-
Window Transmission	503 m²	16013	-	503 m²	41845	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11432	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12730	-	0	0	-
People	101	5729	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	126039	6087	-	61506	0
Zone Conditioning	-	122468	6087	-	59412	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	0	-	667 L/s	0	-
Ventilation Load	667 L/s	8183	2222	667 L/s	19543	0
Ventilation Fan Load	667 L/s	0	-	667 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	130651	8309	-	78955	0
Cooling Coil	-	11842	195	-	0	0
Heating Coil	-	0	-	-	21131	-
Terminal Unit Cooling	-	118809	8225	-	0	0

Terminal Unit Heating	-	0	-	-	57830	-
>> Total Conditioning	-	130651	8420	-	78960	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	661	661	661	152	n/a	n/a
March	1116	1116	1116	259	n/a	n/a
April	7937	7937	7937	1854	n/a	n/a
May	20653	20653	20653	4838	n/a	n/a
June	33716	33716	33716	8045	n/a	n/a
July	39447	39447	39447	9630	n/a	n/a
August	39959	39959	39959	9790	n/a	n/a
September	25818	25818	25818	6147	n/a	n/a
October	13350	13350	13350	3112	n/a	n/a
November	3492	3492	3492	808	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	186149	186149	186149	44636	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **18,0 / 16,8** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,1** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 11,1 K drop **0,46** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 22,0** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,00** BHP
Fan motor kW **0,00** kW
Fan static **0** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for Vake

Project Name: Vake_walls_insulation

05.19.2017

Prepared by:

07:41

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,5 °C / 21,7 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	42737	-	503 m²	-	-
Wall Transmission	369 m²	4855	-	369 m²	13009	-
Roof Transmission	500 m²	6389	-	500 m²	6651	-
Window Transmission	503 m²	6431	-	503 m²	16805	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11432	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12730	-	0	0	-
People	101	5729	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	90303	6087	-	36466	0
Zone Conditioning	-	88129	6087	-	35544	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	0	-	667 L/s	0	-
Ventilation Load	667 L/s	8198	2187	667 L/s	19570	0
Ventilation Fan Load	667 L/s	0	-	667 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	96327	8274	-	55114	0
Cooling Coil	-	11842	195	-	0	0
Heating Coil	-	0	-	-	21131	-
Terminal Unit Cooling	-	84486	8112	-	0	0

Terminal Unit Heating	-	0	-	-	33989	-
>> Total Conditioning	-	96327	8306	-	55120	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	775	775	775	178	n/a	n/a
March	1460	1460	1460	339	n/a	n/a
April	10421	10421	10421	2434	n/a	n/a
May	27121	27121	27121	6351	n/a	n/a
June	44427	44427	44427	10598	n/a	n/a
July	50957	50957	50957	12437	n/a	n/a
August	50762	50762	50762	12421	n/a	n/a
September	33473	33473	33473	7971	n/a	n/a
October	16862	16862	16862	3933	n/a	n/a
November	4079	4079	4079	946	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	240338	240338	240338	57607	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **18,0 / 16,8** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,1** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 11,1 K drop **0,46** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 22,0** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,00** BHP
Fan motor kW **0,00** kW
Fan static **0** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for Vake

Project Name: Vake_walls&roof_insulation

05.19.2017

Prepared by:

07:43

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 34,1 °C / 21,7 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m?	68061	-	503 m?	-	-
Wall Transmission	369 m?	1065	-	369 m?	2560	-
Roof Transmission	500 m?	6277	-	500 m?	6651	-
Window Transmission	503 m?	16918	-	503 m?	41845	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	791 m?	0	-	791 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13776 W	11432	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12730	-	0	0	-
People	101	5729	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	122212	6087	-	51056	0
Zone Conditioning	-	120025	6087	-	49135	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	0	-	667 L/s	0	-
Ventilation Load	667 L/s	8642	1958	667 L/s	19537	0
Ventilation Fan Load	667 L/s	0	-	667 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	128667	8045	-	68673	0
Cooling Coil	-	12266	0	-	0	0
Heating Coil	-	0	-	-	21131	-
Terminal Unit Cooling	-	116401	8166	-	0	0

Terminal Unit Heating	-	0	-	-	47547	-
>> Total Conditioning	-	128667	8166	-	68678	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	826	826	826	190	n/a	n/a
March	1492	1492	1492	347	n/a	n/a
April	10509	10509	10509	2461	n/a	n/a
May	26801	26801	26801	6281	n/a	n/a
June	43369	43369	43369	10347	n/a	n/a
July	49520	49520	49520	12090	n/a	n/a
August	49522	49522	49522	12128	n/a	n/a
September	32924	32924	32924	7839	n/a	n/a
October	17075	17075	17075	3982	n/a	n/a
November	4302	4302	4302	997	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	236340	236340	236340	56661	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **18,0 / 16,8** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,1** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 11,1 K drop **0,46** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 22,0** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,00** BHP
Fan motor kW **0,00** kW
Fan static **0** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for Vake

Project Name: Vake_rebuild

05.19.2017

Prepared by:

07:45

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 34,1 °C / 21,7 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	68061	-	503 m²	-	-
Wall Transmission	369 m²	1065	-	369 m²	2560	-
Roof Transmission	500 m²	1929	-	500 m²	2566	-
Window Transmission	503 m²	16918	-	503 m²	41845	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11432	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12730	-	0	0	-
People	101	5729	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	117863	6087	-	46971	0
Zone Conditioning	-	115889	6087	-	45082	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	0	-	667 L/s	0	-
Ventilation Load	667 L/s	8644	1984	667 L/s	19530	0
Ventilation Fan Load	667 L/s	0	-	667 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	124533	8071	-	64612	0
Cooling Coil	-	12266	0	-	0	0
Heating Coil	-	0	-	-	21131	-
Terminal Unit Cooling	-	112267	8173	-	0	0

Terminal Unit Heating	-	0	-	-	43486	-
>> Total Conditioning	-	124533	8173	-	64617	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	1128	1128	1103	270	n/a	n/a
March	1789	1789	1707	421	n/a	n/a
April	10902	10902	10312	2515	n/a	n/a
May	22171	22171	21953	5212	n/a	n/a
June	32191	32191	32169	7703	n/a	n/a
July	35840	35840	35840	8776	n/a	n/a
August	36466	36466	36466	8974	n/a	n/a
September	24789	24789	24789	5896	n/a	n/a
October	15563	15563	15563	3627	n/a	n/a
November	5368	5368	5356	1256	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	186207	186207	185257	44649	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Aug 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **28,6 / 20,1** °C

Leaving DB / WB **18,0 / 16,8** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **11,3** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 11,1 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,2 / 22,0** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,00** BHP
Fan motor kW **0,00** kW
Fan static **0** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for Vake

Project Name: Vake_vent_reclaim

05.19.2017

Prepared by:

07:28

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,8 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	42243	-	503 m²	-	-
Wall Transmission	369 m²	1015	-	369 m²	2560	-
Roof Transmission	500 m²	2101	-	500 m²	2566	-
Window Transmission	503 m²	6170	-	503 m²	16805	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11586	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12799	-	0	0	-
People	101	5830	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	81743	6087	-	21931	0
Zone Conditioning	-	80479	6087	-	21686	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	0	-	667 L/s	0	-
Ventilation Load	667 L/s	3820	2145	667 L/s	9842	0
Ventilation Fan Load	667 L/s	0	-	667 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	84299	8231	-	31528	0
Cooling Coil	-	7450	0	-	0	0
Heating Coil	-	0	-	-	11288	-
Terminal Unit Cooling	-	76849	8344	-	0	0

Terminal Unit Heating	-	0	-	-	20246	-
>> Total Conditioning	-	84299	8344	-	31534	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	702	702	702	161	n/a	n/a
March	1514	1514	1514	352	n/a	n/a
April	10707	10707	10707	2504	n/a	n/a
May	27471	27471	27471	6431	n/a	n/a
June	44977	44977	44977	10724	n/a	n/a
July	51915	51915	51915	12661	n/a	n/a
August	51686	51686	51686	12639	n/a	n/a
September	33881	33881	33881	8063	n/a	n/a
October	16780	16780	16780	3914	n/a	n/a
November	4071	4071	4071	944	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	243705	243705	243705	58395	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Aug 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **28,6 / 20,1** °C

Leaving DB / WB **18,0 / 16,8** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **11,4** kW
Coil L/s at Des Htg **667** L/s
Max coil L/s **667** L/s
Water flow @ 11,1 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,1 / 22,0** °C

Ventilation Fan Sizing Data

Actual max L/s **667** L/s
Standard L/s **632** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,00** BHP
Fan motor kW **0,00** kW
Fan static **0** Pa

Outdoor Ventilation Air Data

Design airflow L/s **667** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,58** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Didube_as_built

05.17.2017

Prepared by:

11:14

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,5 °C / 21,7 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	503 m²	68891	-	503 m²	-	-
Wall Transmission	369 m²	4855	-	369 m²	13009	-
Roof Transmission	500 m²	6389	-	500 m²	6651	-
Window Transmission	503 m²	16013	-	503 m²	41845	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	791 m²	0	-	791 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13776 W	11432	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13776 W	12730	-	0	0	-
People	101	5729	6087	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	126039	6087	-	61506	0
Zone Conditioning	-	122468	6087	-	59412	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	667 L/s	0	-	667 L/s	0	-
Ventilation Load	667 L/s	4091	2221	667 L/s	9772	0
Ventilation Fan Load	667 L/s	0	-	667 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	126560	8307	-	69183	0
Cooling Coil	-	7751	0	-	0	0
Heating Coil	-	0	-	-	11359	-
Terminal Unit Cooling	-	118809	8419	-	0	0

Terminal Unit Heating	-	0	-	-	57830	-
>> Total Conditioning	-	126560	8419	-	69189	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

დანართი 22: დიდუბის რაიონის გამგეობის შენობის
ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1389	1389	1389	322	n/a	n/a
April	10262	10262	10262	2383	n/a	n/a
May	29210	29210	29210	6832	n/a	n/a
June	47766	47766	47766	11410	n/a	n/a
July	57301	57301	57301	13967	n/a	n/a
August	55112	55112	55112	13463	n/a	n/a
September	35464	35464	35464	8475	n/a	n/a
October	16765	16765	16765	3933	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	253267	253267	253267	60785	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Didube_as_built

05.17.2017

Prepared by:

11:14

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	7343
February	0	8294	0	7728
March	24	0	1364	6621
April	171	0	10091	0
May	791	0	28418	0
June	2782	0	44983	0
July	5985	0	51316	0
August	7241	0	47871	0
September	2321	0	33142	0
October	600	0	16165	321
November	0	4224	0	1467
December	0	7218	0	6418
Total	19917	28745	233350	29899

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW
 Sensible coil load **12,8** kW
 Coil L/s at Jul 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,56** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_new_windows

05.17.2017

Prepared by:

11:17

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m²	89758	-	571 m²	-	-
Wall Transmission	290 m²	3878	-	290 m²	10219	-
Roof Transmission	500 m²	7017	-	500 m²	6651	-
Window Transmission	571 m²	22347	-	571 m²	65844	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	15285	597	10%	8271	0
>> Total Zone Loads	-	168139	6567	-	90986	0
Zone Conditioning	-	164201	6567	-	88328	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	5984	2568	652 L/s	19664	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	171393	9135	-	106784	0
Cooling Coil	-	10757	1065	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	160636	8150	-	0	0

Terminal Unit Heating	-	0	-	-	86711	-
>> Total Conditioning	-	171393	9215	-	106790	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1221	1221	1221	283	n/a	n/a
April	8673	8673	8673	2016	n/a	n/a
May	22556	22556	22556	5277	n/a	n/a
June	35436	35436	35436	8470	n/a	n/a
July	42234	42234	42234	10302	n/a	n/a
August	41431	41431	41431	10125	n/a	n/a
September	26829	26829	26829	6411	n/a	n/a
October	14139	14139	14139	3306	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	192519	192519	192519	46191	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_new_windows

05.17.2017

Prepared by:

11:17

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	1525
February	0	8294	0	2181
March	24	0	1197	3165
April	171	0	8502	0
May	791	0	21764	0
June	2782	0	32654	0
July	5985	0	36249	0
August	7241	0	34190	0
September	2321	0	24507	0
October	600	0	13540	146
November	0	4224	0	147
December	0	7218	0	1352
Total	19917	28745	172603	8515

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m²
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW
 Sensible coil load **12,8** kW
 Coil L/s at Jul 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,56** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_walls_insulation

05.17.2017

Prepared by:

11:23

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m?	59304	-	571 m?	-	-
Wall Transmission	290 m?	3878	-	290 m?	10219	-
Roof Transmission	500 m?	7017	-	500 m?	6651	-
Window Transmission	571 m?	6475	-	571 m?	19077	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	772 m?	0	-	772 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	10653	597	10%	3595	0
>> Total Zone Loads	-	117181	6567	-	39542	0
Zone Conditioning	-	114242	6567	-	39531	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	5985	2475	652 L/s	19839	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	121435	9041	-	58161	0
Cooling Coil	-	10757	1065	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	110678	8109	-	0	0

Terminal Unit Heating	-	0	-	-	38088	-
>> Total Conditioning	-	121435	9174	-	58167	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1507	1507	1507	350	n/a	n/a
April	10920	10920	10920	2554	n/a	n/a
May	29659	29659	29659	6964	n/a	n/a
June	47274	47274	47274	11292	n/a	n/a
July	56105	56105	56105	13745	n/a	n/a
August	53805	53805	53805	13187	n/a	n/a
September	35042	35042	35042	8338	n/a	n/a
October	17342	17342	17342	4045	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	251654	251654	251654	60475	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_walls_insulation

05.17.2017

Prepared by:

11:23

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	5051
February	0	8294	0	5632
March	24	0	1483	4968
April	171	0	10749	0
May	791	0	28867	0
June	2782	0	44492	0
July	5985	0	50120	0
August	7241	0	46564	0
September	2321	0	32720	0
October	600	0	16742	247
November	0	4224	0	873
December	0	7218	0	4499
Total	19917	28745	231738	21271

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1346,8** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW

Sensible heat ratio **0,923**

Sensible coil load **12,8** kW

Water flow @ 6,0 K rise **0,56** L/s

Coil L/s at Jul 1500 **652** L/s

Max coil L/s **652** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Didube_as_build

05.17.2017

Prepared by: AECOM

11:26

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m²	95596	-	571 m²	-	-
Wall Transmission	290 m²	779	-	290 m²	2011	-
Roof Transmission	500 m²	7017	-	500 m²	6651	-
Window Transmission	571 m²	16122	-	571 m²	47502	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	14937	597	10%	5616	0
>> Total Zone Loads	-	164304	6567	-	61781	0
Zone Conditioning	-	159261	6567	-	61968	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	5909	2373	652 L/s	19885	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	166379	8940	-	80645	0
Cooling Coil	-	10757	1065	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	155622	7938	-	0	0

Terminal Unit Heating	-	0	-	-	60572	-
>> Total Conditioning	-	166379	9003	-	80651	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1534	1534	1534	356	n/a	n/a
April	11015	11015	11012	2577	n/a	n/a
May	29323	29323	29323	6884	n/a	n/a
June	46196	46196	46196	11027	n/a	n/a
July	54638	54638	54638	13366	n/a	n/a
August	52530	52530	52530	12858	n/a	n/a
September	34465	34465	34465	8203	n/a	n/a
October	17545	17545	17545	4091	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	247246	247246	247242	59362	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Didube_as_build

05.17.2017

Prepared by: AECOM

11:26

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	3722
February	0	8294	0	4472
March	24	0	1509	4149
April	171	0	10844	0
May	791	0	28532	0
June	2782	0	43414	0
July	5985	0	48653	0
August	7241	0	45289	0
September	2321	0	32144	0
October	600	0	16945	202
November	0	4224	0	501
December	0	7218	0	3302
Total	19917	28745	227329	16349

Air System Information

Air System Name **As_build**
Equipment Class **TERM**
Air System Type **2P-FC**

Number of zones **3**
Floor Area **1346,8** m²
Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW
Sensible coil load **12,8** kW
Coil L/s at Jul 1500 **652** L/s
Max coil L/s **652** L/s
Sensible heat ratio **0,923**

Water flow @ 6,0 K rise **0,56** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_rebuild

05.18.2017

Prepared by:

02:26

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m?	95596	-	571 m?	-	-
Wall Transmission	290 m?	779	-	290 m?	2011	-
Roof Transmission	500 m?	2218	-	500 m?	2554	-
Window Transmission	571 m?	16122	-	571 m?	47502	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	772 m?	0	-	772 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	14457	597	10%	5207	0
>> Total Zone Loads	-	159026	6567	-	57274	0
Zone Conditioning	-	155672	6567	-	57439	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	5969	2548	652 L/s	19880	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	162849	9115	-	76111	0
Cooling Coil	-	10757	1065	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	152091	8278	-	0	0

Terminal Unit Heating	-	0	-	-	56038	-
>> Total Conditioning	-	162849	9342	-	76117	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1909	1909	1876	451	n/a	n/a
April	11704	11704	11449	2753	n/a	n/a
May	24042	24042	23979	5654	n/a	n/a
June	34027	34027	34020	8127	n/a	n/a
July	39098	39098	39098	9528	n/a	n/a
August	38389	38389	38389	9374	n/a	n/a
September	25840	25840	25840	6162	n/a	n/a
October	16091	16091	16091	3750	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	191102	191102	190742	45799	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_rebuild

05.18.2017

Prepared by:

02:26

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	1926	0	66
February	0	1918	0	180
March	24	0	1885	15
April	170	0	11534	0
May	761	0	23282	0
June	2582	0	31445	0
July	5474	0	33625	0
August	6661	0	31728	0
September	2190	0	23651	0
October	598	0	15493	2
November	0	269	0	0
December	0	1268	0	48
Total	18460	5381	172643	311

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m²
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **9,2** kW
 Sensible coil load **8,6** kW
 Coil L/s at Jun 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,929**
 Water flow @ 6,0 K rise **0,37** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **10,2** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,12** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,6 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_vent_reclaim

05.18.2017

Prepared by:

02:22

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m²	59304	-	571 m²	-	-
Wall Transmission	290 m²	779	-	290 m²	2011	-
Roof Transmission	500 m²	2232	-	500 m²	2566	-
Window Transmission	571 m²	6475	-	571 m²	19077	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	9864	597	10%	2365	0
>> Total Zone Loads	-	108508	6567	-	26020	0
Zone Conditioning	-	106121	6567	-	25893	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	2991	2474	652 L/s	9927	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	110321	9041	-	34611	0
Cooling Coil	-	7766	500	-	0	0
Heating Coil	-	0	-	-	10153	-
Terminal Unit Cooling	-	102555	8650	-	0	0

Terminal Unit Heating	-	0	-	-	24462	-
>> Total Conditioning	-	110321	9150	-	34614	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1613	1613	1613	374	n/a	n/a
April	11425	11425	11425	2655	n/a	n/a
May	30116	30116	30116	7042	n/a	n/a
June	47799	47799	47799	11412	n/a	n/a
July	56822	56822	56822	13843	n/a	n/a
August	54578	54578	54578	13327	n/a	n/a
September	35432	35432	35432	8463	n/a	n/a
October	17462	17462	17462	4090	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	255245	255245	255245	61205	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Didube_vent_reclaim

05.18.2017

Prepared by:

02:22

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	3068	0	7321
February	0	2735	0	7715
March	24	0	1589	3737
April	170	0	11255	0
May	760	0	29357	0
June	2581	0	45218	0
July	5472	0	51350	0
August	6658	0	47919	0
September	2188	0	33244	0
October	597	0	16864	80
November	0	1056	0	1395
December	0	2245	0	6367
Total	18450	9105	236795	26616

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m²
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **9,3** kW
 Sensible coil load **8,6** kW
 Coil L/s at Jun 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,929**
 Water flow @ 6,0 K rise **0,37** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **10,2** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,12** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,6 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Nadzaladevi_as_built

05.17.2017

Prepared by:

02:51

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m?	95596	-	571 m?	-	-
Wall Transmission	290 m?	3878	-	290 m?	10219	-
Roof Transmission	500 m?	7016	-	500 m?	6651	-
Window Transmission	571 m?	16122	-	571 m?	47502	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	772 m?	0	-	772 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	15247	597	10%	6437	0
>> Total Zone Loads	-	167713	6567	-	70810	0
Zone Conditioning	-	163196	6567	-	70642	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	2966	2450	652 L/s	9924	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	167371	9017	-	79358	0
Cooling Coil	-	7791	505	-	0	0
Heating Coil	-	0	-	-	10155	-
Terminal Unit Cooling	-	159580	8856	-	0	0

Terminal Unit Heating	-	0	-	-	69210	-
>> Total Conditioning	-	167371	9361	-	79365	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

დანართი 23: ნაძალადევის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	627	627	627	147	n/a	n/a
April	4718	4718	4718	1102	n/a	n/a
May	16363	16363	16363	3848	n/a	n/a
June	33064	33064	33064	7935	n/a	n/a
July	44882	44882	44882	10960	n/a	n/a
August	45520	45520	45520	11126	n/a	n/a
September	24697	24697	24697	5920	n/a	n/a
October	9459	9459	9459	2236	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	179330	179330	179330	43275	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Nadzaladevi_as_built

05.17.2017

Prepared by:

02:51

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9799	0	9628
February	0	9022	0	9677
March	27	0	600	12229
April	186	0	4532	0
May	861	0	15502	0
June	3027	0	30038	0
July	6510	0	38372	0
August	7877	0	37643	0
September	2525	0	22172	0
October	652	0	8806	804
November	0	4595	0	2983
December	0	7852	0	7968
Total	21665	31268	157665	43289

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **41**
 Floor Area **840,2** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **15,1** kW
 Sensible coil load **14,0** kW
 Coil L/s at Jul 1500 **710** L/s
 Max coil L/s **710** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,60** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,8** kW
Coil L/s at Des Htg **710** L/s
Max coil L/s **710** L/s
Water flow @ 20,0 K drop **0,26** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **710** L/s
L/(s·m?) **0,84** L/(s·m?)

L/s/person **5,14** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_new_windows

05.17.2017

Prepared by:

03:08

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	43617	-	330 m²	-	-
Wall Transmission	501 m²	6564	-	501 m²	17658	-
Roof Transmission	432 m²	5747	-	432 m²	5741	-
Window Transmission	330 m²	14794	-	330 m²	38054	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	183 m²	0	-	183 m²	0	-
Partitions	988 m²	10776	-	988 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	9994 W	8405	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	14985 W	13921	-	0	0	-
People	138	7946	8296	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	11177	830	10%	6145	0
>> Total Zone Loads	-	122948	9126	-	67599	0
Zone Conditioning	-	117698	9126	-	65490	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	710 L/s	657	-	710 L/s	-657	-
Ventilation Load	710 L/s	7914	983	710 L/s	21366	0
Ventilation Fan Load	710 L/s	657	-	710 L/s	-657	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	126926	10109	-	85541	0
Cooling Coil	-	13109	1007	-	0	0
Heating Coil	-	0	-	-	21842	-
Terminal Unit Cooling	-	113838	9294	-	0	0

Terminal Unit Heating	-	0	-	-	63721	-
>> Total Conditioning	-	126947	10301	-	85563	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	630	630	630	147	n/a	n/a
April	4534	4534	4534	1055	n/a	n/a
May	14216	14216	14216	3338	n/a	n/a
June	27295	27295	27295	6547	n/a	n/a
July	37029	37029	37029	9040	n/a	n/a
August	38124	38124	38124	9324	n/a	n/a
September	20835	20835	20835	4988	n/a	n/a
October	9057	9057	9057	2129	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	151721	151721	151721	36568	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_new_windows

05.17.2017

Prepared by:

03:08

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9799	0	3534
February	0	9022	0	3952
March	27	0	604	7677
April	186	0	4348	0
May	861	0	13355	0
June	3027	0	24269	0
July	6510	0	30519	0
August	7877	0	30248	0
September	2525	0	18310	0
October	652	0	8404	551
November	0	4595	0	994
December	0	7852	0	2963
Total	21665	31268	130056	19671

Air System Information

Air System Name	As_build	Number of zones	41
Equipment Class	TERM	Floor Area	840,2 m²
Air System Type	2P-FC	Location	Tbilisi, Georgia

Sizing Calculation Information

Calculation Months	Jan to Dec	Zone L/s Sizing	Sum of space airflow rates
Sizing Data	Calculated	Space L/s Sizing	Individual peak space loads

Cooling Coil Sizing Data

Total coil load	15,1 kW	Sensible heat ratio	0,923
Sensible coil load	14,0 kW	Water flow @ 6,0 K rise	0,60 L/s
Coil L/s at Jul 1500	710 L/s		
Max coil L/s	710 L/s		

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,8** kW
Coil L/s at Des Htg **710** L/s
Max coil L/s **710** L/s
Water flow @ 20,0 K drop **0,26** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **710** L/s
L/(s·m?) **0,84** L/(s·m?)

L/s/person **5,14** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_walls_insulation

05.17.2017

Prepared by:

03:43

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	28818	-	330 m²	-	-
Wall Transmission	501 m²	6564	-	501 m²	17658	-
Roof Transmission	432 m²	5747	-	432 m²	5741	-
Window Transmission	330 m²	4286	-	330 m²	11025	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	183 m²	0	-	183 m²	0	-
Partitions	988 m²	10776	-	988 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	9994 W	8405	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	14985 W	13921	-	0	0	-
People	138	7946	8296	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	8646	830	10%	3442	0
>> Total Zone Loads	-	95111	9126	-	37867	0
Zone Conditioning	-	90928	9126	-	36842	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	710 L/s	657	-	710 L/s	-657	-
Ventilation Load	710 L/s	7940	900	710 L/s	21472	0
Ventilation Fan Load	710 L/s	657	-	710 L/s	-657	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	100182	10026	-	57000	0
Cooling Coil	-	13109	1007	-	0	0
Heating Coil	-	0	-	-	21842	-
Terminal Unit Cooling	-	87094	9203	-	0	0

Terminal Unit Heating	-	0	-	-	35180	-
>> Total Conditioning	-	100203	10210	-	57022	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	830	830	830	193	n/a	n/a
April	6059	6059	6059	1408	n/a	n/a
May	18400	18400	18400	4316	n/a	n/a
June	33686	33686	33686	8072	n/a	n/a
July	43618	43618	43618	10654	n/a	n/a
August	44080	44080	44080	10782	n/a	n/a
September	25416	25416	25416	6083	n/a	n/a
October	11435	11435	11435	2685	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	183524	183524	183524	44192	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_walls_insulation

05.17.2017

Prepared by:

03:43

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9799	0	3003
February	0	9022	0	3195
March	27	0	803	6586
April	186	0	5873	0
May	861	0	17539	0
June	3027	0	30659	0
July	6510	0	37108	0
August	7877	0	36203	0
September	2525	0	22891	0
October	652	0	10783	556
November	0	4595	0	757
December	0	7852	0	2643
Total	21665	31268	161859	16740

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **41**
 Floor Area **840,2** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **15,1** kW
 Sensible coil load **14,0** kW
 Coil L/s at Jul 1500 **710** L/s
 Max coil L/s **710** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,60** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,8** kW
Coil L/s at Des Htg **710** L/s
Max coil L/s **710** L/s
Water flow @ 20,0 K drop **0,26** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **710** L/s
L/(s·m?) **0,84** L/(s·m?)

L/s/person **5,14** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_walls&roof_insulation

05.17.2017

Prepared by:

09:49

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,8 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	47304	-	330 m²	-	-
Wall Transmission	501 m²	1355	-	501 m²	3605	-
Roof Transmission	432 m²	5841	-	432 m²	5741	-
Window Transmission	330 m²	10079	-	330 m²	27453	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	183 m²	0	-	183 m²	0	-
Partitions	988 m²	10605	-	988 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	9994 W	8405	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	14985 W	13921	-	0	0	-
People	138	7946	8296	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	10546	830	10%	3680	0
>> Total Zone Loads	-	116002	9126	-	40479	0
Zone Conditioning	-	111892	9126	-	39624	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	710 L/s	657	-	710 L/s	-657	-
Ventilation Load	710 L/s	7477	1254	710 L/s	21537	0
Ventilation Fan Load	710 L/s	657	-	710 L/s	-657	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	120684	10380	-	59847	0
Cooling Coil	-	12658	1336	-	0	0
Heating Coil	-	0	-	-	21842	-
Terminal Unit Cooling	-	108067	9167	-	0	0

Terminal Unit Heating	-	0	-	-	38006	-
>> Total Conditioning	-	120725	10502	-	59848	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	706	706	706	164	n/a	n/a
April	5118	5118	5118	1191	n/a	n/a
May	16314	16314	16314	3832	n/a	n/a
June	31267	31267	31267	7503	n/a	n/a
July	41632	41632	41632	10178	n/a	n/a
August	42429	42429	42429	10385	n/a	n/a
September	23706	23706	23706	5679	n/a	n/a
October	10180	10180	10180	2395	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	171352	171352	171352	41329	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_walls&roof_insulation

05.17.2017

Prepared by:

09:49

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9799	0	5237
February	0	9022	0	5278
March	27	0	680	8638
April	186	0	4932	0
May	861	0	15453	0
June	3027	0	28241	0
July	6510	0	35122	0
August	7877	0	34552	0
September	2525	0	21181	0
October	652	0	9527	688
November	0	4595	0	1585
December	0	7852	0	4412
Total	21665	31268	149687	25839

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **41**
 Floor Area **840,2** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **15,1** kW
 Sensible coil load **14,0** kW
 Coil L/s at Jul 1500 **710** L/s
 Max coil L/s **710** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,60** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **21,8** kW
Coil L/s at Des Htg **710** L/s
Max coil L/s **710** L/s
Water flow @ 20,0 K drop **0,26** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **710** L/s
L/(s·m?) **0,84** L/(s·m?)

L/s/person **5,14** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_as_built

05.18.2017

Prepared by: AECOM

03:09

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m?	46454	-	330 m?	-	-
Wall Transmission	501 m?	1411	-	501 m?	3605	-
Roof Transmission	432 m?	1781	-	432 m?	2236	-
Window Transmission	330 m?	10673	-	330 m?	27453	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	183 m?	0	-	183 m?	0	-
Partitions	988 m?	10776	-	988 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	9994 W	8405	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	14985 W	13921	-	0	0	-
People	138	7946	8296	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	10137	830	10%	3329	0
>> Total Zone Loads	-	111504	9126	-	36623	0
Zone Conditioning	-	107417	9126	-	36027	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	710 L/s	657	-	710 L/s	-657	-
Ventilation Load	710 L/s	7932	735	710 L/s	21551	0
Ventilation Fan Load	710 L/s	657	-	710 L/s	-657	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	116663	9861	-	56263	0
Cooling Coil	-	13109	1007	-	0	0
Heating Coil	-	0	-	-	21842	-
Terminal Unit Cooling	-	103594	9057	-	0	0

Terminal Unit Heating	-	0	-	-	34439	-
>> Total Conditioning	-	116702	10064	-	56281	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	798	798	798	185	n/a	n/a
April	5499	5499	5499	1278	n/a	n/a
May	14663	14663	14663	3439	n/a	n/a
June	25407	25407	25407	6088	n/a	n/a
July	33249	33249	33249	8128	n/a	n/a
August	34456	34456	34456	8448	n/a	n/a
September	19759	19759	19759	4725	n/a	n/a
October	10260	10260	10260	2395	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	144092	144092	144092	34687	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_as_built

05.18.2017

Prepared by: AECOM

03:09

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	3586	0	316
February	0	3450	0	424
March	27	0	771	1274
April	183	0	5317	0
May	822	0	13841	0
June	2799	0	22608	0
July	5942	0	27307	0
August	7240	0	27216	0
September	2373	0	17386	0
October	648	0	9612	114
November	0	1435	0	56
December	0	2869	0	297
Total	20033	11341	124058	2481

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **41**
 Floor Area **840,2** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **10,1** kW
 Sensible coil load **9,3** kW
 Coil L/s at Jun 1500 **710** L/s
 Max coil L/s **710** L/s

Sensible heat ratio **0,929**
 Water flow @ 6,0 K rise **0,40** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **11,0** kW
Coil L/s at Des Htg **710** L/s
Max coil L/s **710** L/s
Water flow @ 20,0 K drop **0,13** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,6 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **710** L/s
L/(s·m?) **0,84** L/(s·m?)

L/s/person **5,14** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_vent_reclaim

05.18.2017

Prepared by:

02:48

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,8 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m?	29345	-	330 m?	-	-
Wall Transmission	501 m?	1303	-	501 m?	3475	-
Roof Transmission	432 m?	1813	-	432 m?	2215	-
Window Transmission	330 m?	4048	-	330 m?	11025	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	183 m?	0	-	183 m?	0	-
Partitions	988 m?	10605	-	988 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	9994 W	8405	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	14985 W	13921	-	0	0	-
People	138	7946	8296	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	7739	830	10%	1672	0
>> Total Zone Loads	-	85126	9126	-	18387	0
Zone Conditioning	-	81596	9126	-	18057	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	710 L/s	657	-	710 L/s	-657	-
Ventilation Load	710 L/s	3752	1194	710 L/s	10797	0
Ventilation Fan Load	710 L/s	657	-	710 L/s	-657	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	86663	10320	-	27540	0
Cooling Coil	-	8906	632	-	0	0
Heating Coil	-	0	-	-	11045	-
Terminal Unit Cooling	-	77795	9712	-	0	0

Terminal Unit Heating	-	0	-	-	16495	-
>> Total Conditioning	-	86701	10344	-	27540	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	665	665	665	156	n/a	n/a
April	5039	5039	5039	1174	n/a	n/a
May	16687	16687	16687	3920	n/a	n/a
June	32926	32926	32926	7896	n/a	n/a
July	44349	44349	44349	10822	n/a	n/a
August	44947	44947	44947	10981	n/a	n/a
September	24595	24595	24595	5892	n/a	n/a
October	9732	9732	9732	2296	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	178940	178940	178940	43138	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Nadzaladevi_vent_reclaim

05.18.2017

Prepared by:

02:48

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	4487	0	9621
February	0	4210	0	9653
March	27	0	639	8295
April	182	0	4856	0
May	821	0	15866	0
June	2797	0	30128	0
July	5940	0	38409	0
August	7237	0	37710	0
September	2370	0	22225	0
October	648	0	9084	430
November	0	1960	0	2956
December	0	3613	0	7952
Total	20022	14271	158917	38907

Air System Information

Air System Name	As_build	Number of zones	41
Equipment Class	TERM	Floor Area	840,2 m²
Air System Type	2P-FC	Location	Tbilisi, Georgia

Sizing Calculation Information

Calculation Months	Jan to Dec	Zone L/s Sizing	Sum of space airflow rates
Sizing Data	Calculated	Space L/s Sizing	Individual peak space loads

Cooling Coil Sizing Data

Total coil load	10,0 kW	Sensible heat ratio	0,929
Sensible coil load	9,3 kW	Water flow @ 6,0 K rise	0,40 L/s
Coil L/s at Jun 1500	710 L/s		
Max coil L/s	710 L/s		

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **11,2** kW
Coil L/s at Des Htg **710** L/s
Max coil L/s **710** L/s
Water flow @ 20,0 K drop **0,13** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,5 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **710** L/s
Standard L/s **673** L/s
Actual max L/(s·m?) **0,84** L/(s·m?)

Fan motor BHP **0,83** BHP
Fan motor kW **0,66** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **710** L/s
L/(s·m?) **0,84** L/(s·m?)

L/s/person **5,14** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Mtatsminda_as_build

05.18.2017

Prepared by:

09:00

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m?	43617	-	330 m?	-	-
Wall Transmission	501 m?	6564	-	501 m?	17658	-
Roof Transmission	432 m?	5747	-	432 m?	5741	-
Window Transmission	330 m?	14794	-	330 m?	38054	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	183 m?	0	-	183 m?	0	-
Partitions	988 m?	10776	-	988 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	9994 W	8405	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	14985 W	13921	-	0	0	-
People	138	7946	8296	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	11177	830	10%	6145	0
>> Total Zone Loads	-	122948	9126	-	67599	0
Zone Conditioning	-	117698	9126	-	65490	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	710 L/s	657	-	710 L/s	-657	-
Ventilation Load	710 L/s	3957	908	710 L/s	10683	0
Ventilation Fan Load	710 L/s	657	-	710 L/s	-657	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	122969	10033	-	74858	0
Cooling Coil	-	9152	267	-	0	0
Heating Coil	-	0	-	-	11159	-
Terminal Unit Cooling	-	113838	9960	-	0	0

Terminal Unit Heating	-	0	-	-	63721	-
>> Total Conditioning	-	122990	10227	-	74880	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

დანართი 24: მთაწმინდის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1853	1853	1853	430	n/a	n/a
April	13911	13911	13911	3233	n/a	n/a
May	42581	42581	42581	9974	n/a	n/a
June	73830	73830	73830	17652	n/a	n/a
July	94281	94281	94281	22947	n/a	n/a
August	97242	97242	97242	23705	n/a	n/a
September	60715	60715	60715	14484	n/a	n/a
October	28996	28996	28996	6776	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	413410	413410	413410	99201	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Mtatsminda_as_build

05.18.2017

Prepared by:

09:00

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	24109	0	5164
February	0	22198	0	7353
March	137	0	1716	16329
April	952	0	12959	0
May	4021	0	38561	0
June	12028	0	61802	0
July	23955	0	70327	0
August	27711	0	69532	0
September	10998	0	49717	0
October	3510	0	25486	754
November	0	11306	0	692
December	0	19318	0	4589
Total	83311	76932	330099	34881

Air System Information

Air System Name As_build	Number of zones 5
Equipment Class TERM	Floor Area 3174,9 m ²
Air System Type 2P-FC	Location Tbilisi, Georgia

Sizing Calculation Information

Calculation Months Jan to Dec	Zone L/s Sizing Sum of space airflow rates
Sizing Data Calculated	Space L/s Sizing Individual peak space loads

Cooling Coil Sizing Data

Total coil load 48,1 kW	Water flow @ 6,0 K rise 1,92 L/s
Sensible coil load 38,4 kW	
Coil L/s at Jul 1500 1746 L/s	
Max coil L/s 1746 L/s	
Sensible heat ratio 0,798	

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **15,2 / 14,1** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **53,7** kW
Coil L/s at Des Htg **1746** L/s
Max coil L/s **1746** L/s
Water flow @ 20,0 K drop **0,64** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1746** L/s
L/(s·m?) **0,55** L/(s·m?)

L/s/person **5,50** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_new_windows

05.18.2017

Prepared by:

09:08

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	577 m?	88413	-	577 m?	-	-
Wall Transmission	2073 m?	16497	-	2073 m?	40959	-
Roof Transmission	1155 m?	15377	-	1155 m?	15362	-
Window Transmission	577 m?	18454	-	577 m?	47467	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	145 m?	0	-	145 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	31749 W	26701	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	31749 W	29496	-	0	0	-
People	317	18270	19075	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	21321	1907	10%	10379	0
>> Total Zone Loads	-	234530	20982	-	114167	0
Zone Conditioning	-	228669	20982	-	111967	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Ventilation Load	1746 L/s	19449	4838	1746 L/s	52236	0
Ventilation Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	251352	25820	-	160970	0
Cooling Coil	-	36249	9375	-	0	0
Heating Coil	-	0	-	-	53739	-
Terminal Unit Cooling	-	215103	16501	-	0	0

Terminal Unit Heating	-	0	-	-	107264	-
>> Total Conditioning	-	251352	25876	-	161003	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1499	1499	1499	348	n/a	n/a
April	11209	11209	11209	2605	n/a	n/a
May	34569	34569	34569	8102	n/a	n/a
June	60065	60065	60065	14369	n/a	n/a
July	78093	78093	78093	19006	n/a	n/a
August	81783	81783	81783	19944	n/a	n/a
September	49893	49893	49893	11901	n/a	n/a
October	24910	24910	24910	5814	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	342021	342021	342021	82088	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jul 1500**
 OA DB / WB **34,4 / 21,8** °C
 Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **15,2 / 14,1** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **53,7** kW
 Coil L/s at Des Htg **1746** L/s
 Max coil L/s **1746** L/s
 Water flow @ 20,0 K drop **0,64** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1746** L/s
 Standard L/s **1655** L/s
 Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
 Fan motor kW **1,62** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1746** L/s
 Standard L/s **1655** L/s
 Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
 Fan motor kW **1,62** kW
 Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1746** L/s
 L/(s·m?) **0,55** L/(s·m?)

L/s/person **5,50** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_walls_insulation

05.18.2017

Prepared by:

09:15

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	577 m²	55421	-	577 m²	-	-
Wall Transmission	2073 m²	16039	-	2073 m²	40959	-
Roof Transmission	1155 m²	14009	-	1155 m²	15362	-
Window Transmission	577 m²	7495	-	577 m²	19278	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	145 m²	0	-	145 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	31749 W	26701	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	31749 W	29496	-	0	0	-
People	317	18270	19075	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	16743	1907	10%	7560	0
>> Total Zone Loads	-	184175	20982	-	83159	0
Zone Conditioning	-	179772	20982	-	84334	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Ventilation Load	1746 L/s	19520	4716	1746 L/s	52471	0
Ventilation Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	202526	25698	-	133572	0
Cooling Coil	-	36249	9375	-	0	0
Heating Coil	-	0	-	-	53739	-
Terminal Unit Cooling	-	166277	16292	-	0	0

Terminal Unit Heating	-	0	-	-	79833	-
>> Total Conditioning	-	202526	25667	-	133572	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	2502	2502	2502	580	n/a	n/a
April	16951	16951	16951	3946	n/a	n/a
May	44459	44459	44459	10415	n/a	n/a
June	73090	73090	73090	17481	n/a	n/a
July	91168	91168	91168	22222	n/a	n/a
August	93807	93807	93807	22907	n/a	n/a
September	59531	59531	59531	14204	n/a	n/a
October	30957	30957	30957	7227	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	412465	412465	412465	98981	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_walls_insulation

05.18.2017

Prepared by:

09:15

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	24109	0	2457
February	0	22198	0	3997
March	137	0	2366	10604
April	952	0	15999	0
May	4021	0	40438	0
June	12028	0	61062	0
July	23955	0	67213	0
August	27711	0	66097	0
September	10998	0	48532	0
October	3510	0	27447	645
November	0	11306	0	280
December	0	19318	0	2298
Total	83311	76932	329154	20281

Air System Information

Air System Name **As_build**

Number of zones **5**

Equipment Class **TERM**

Floor Area **3174,9** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **48,1** kW

Sensible heat ratio **0,798**

Sensible coil load **38,4** kW

Water flow @ 6,0 K rise **1,92** L/s

Coil L/s at Jul 1500 **1746** L/s

Max coil L/s **1746** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **15,2 / 14,1** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **53,7** kW
Coil L/s at Des Htg **1746** L/s
Max coil L/s **1746** L/s
Water flow @ 20,0 K drop **0,64** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1746** L/s
L/(s·m?) **0,55** L/(s·m?)

L/s/person **5,50** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_walls&roof_insulation

05.18.2017

Prepared by:

09:18

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	577 m?	88413	-	577 m?	-	-
Wall Transmission	2073 m?	10743	-	2073 m?	14351	-
Roof Transmission	1155 m?	15377	-	1155 m?	15362	-
Window Transmission	577 m?	18454	-	577 m?	47467	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	145 m?	0	-	145 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	31749 W	26701	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	31749 W	29496	-	0	0	-
People	317	18270	19075	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	20745	1907	10%	7718	0
>> Total Zone Loads	-	228200	20982	-	84898	0
Zone Conditioning	-	223934	20982	-	82036	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Ventilation Load	1746 L/s	19561	5090	1746 L/s	52401	0
Ventilation Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	246729	26072	-	131203	0
Cooling Coil	-	36249	9375	-	0	0
Heating Coil	-	0	-	-	53739	-
Terminal Unit Cooling	-	210480	16484	-	0	0

Terminal Unit Heating	-	0	-	-	77464	-
>> Total Conditioning	-	246729	25859	-	131203	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	2567	2567	2567	596	n/a	n/a
April	17222	17222	17222	4016	n/a	n/a
May	43647	43647	43647	10229	n/a	n/a
June	70629	70629	70629	16893	n/a	n/a
July	87800	87800	87800	21404	n/a	n/a
August	90880	90880	90880	22198	n/a	n/a
September	58234	58234	58234	13893	n/a	n/a
October	31474	31474	31474	7343	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	402452	402452	402452	96571	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_walls&roof_insulation

05.18.2017

Prepared by:

09:18

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	24109	0	581
February	0	22198	0	1729
March	137	0	2430	8551
April	952	0	16270	0
May	4021	0	39626	0
June	12028	0	58601	0
July	23955	0	63845	0
August	27711	0	63169	0
September	10998	0	47236	0
October	3510	0	27964	528
November	0	11306	0	19
December	0	19318	0	475
Total	83311	76932	319141	11883

Air System Information

Air System Name	As_build	Number of zones	5
Equipment Class	TERM	Floor Area	3174,9 m²
Air System Type	2P-FC	Location	Tbilisi, Georgia

Sizing Calculation Information

Calculation Months	Jan to Dec	Zone L/s Sizing	Sum of space airflow rates
Sizing Data	Calculated	Space L/s Sizing	Individual peak space loads

Cooling Coil Sizing Data

Total coil load	48,1 kW	Water flow @ 6,0 K rise	1,92 L/s
Sensible coil load	38,4 kW		
Coil L/s at Jul 1500	1746 L/s		
Max coil L/s	1746 L/s		
Sensible heat ratio	0,798		

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **15,2 / 14,1** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **53,7** kW
Coil L/s at Des Htg **1746** L/s
Max coil L/s **1746** L/s
Water flow @ 20,0 K drop **0,64** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1746** L/s
L/(s·m?) **0,55** L/(s·m?)

L/s/person **5,50** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_rebuild

05.18.2017

Prepared by:

09:21

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	577 m?	88413	-	577 m?	-	-
Wall Transmission	2073 m?	10743	-	2073 m?	14351	-
Roof Transmission	1155 m?	4766	-	1155 m?	5927	-
Window Transmission	577 m?	18454	-	577 m?	47467	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	145 m?	0	-	145 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	31749 W	26701	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	31749 W	29496	-	0	0	-
People	317	18270	19075	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	19684	1907	10%	6775	0
>> Total Zone Loads	-	216529	20982	-	74520	0
Zone Conditioning	-	213940	20982	-	72177	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Ventilation Load	1746 L/s	19621	5144	1746 L/s	52441	0
Ventilation Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	236795	26126	-	121384	0
Cooling Coil	-	36249	9375	-	0	0
Heating Coil	-	0	-	-	53739	-
Terminal Unit Cooling	-	200546	16989	-	0	0

Terminal Unit Heating	-	0	-	-	67645	-
>> Total Conditioning	-	236795	26364	-	121384	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	3308	3308	3287	796	n/a	n/a
April	19177	19177	18854	4546	n/a	n/a
May	38417	38417	38311	9052	n/a	n/a
June	57108	57108	57108	13674	n/a	n/a
July	70399	70399	70399	17153	n/a	n/a
August	74081	74081	74081	18119	n/a	n/a
September	47393	47393	47393	11295	n/a	n/a
October	29787	29787	29787	6942	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	339670	339670	339220	81576	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_rebuild

05.18.2017

Prepared by:

09:21

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	5771	0	14
February	0	6139	0	85
March	137	0	3171	148
April	947	0	18230	0
May	3937	0	34479	0
June	11477	0	45631	0
July	22555	0	47844	0
August	26200	0	47881	0
September	10635	0	36758	0
October	3505	0	26283	44
November	0	1028	0	0
December	0	4156	0	8
Total	79393	17094	260277	299

Air System Information

Air System Name **As_build**
Equipment Class **TERM**
Air System Type **2P-FC**

Number of zones **5**
Floor Area **3174,9** m²
Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **35,9** kW
Sensible coil load **27,0** kW
Coil L/s at Jun 1500 **1746** L/s
Max coil L/s **1746** L/s
Sensible heat ratio **0,753**

Water flow @ 6,0 K rise **1,43** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **15,2 / 14,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **27,4** kW
Coil L/s at Des Htg **1746** L/s
Max coil L/s **1746** L/s
Water flow @ 20,0 K drop **0,33** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,5 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1746** L/s
L/(s·m?) **0,55** L/(s·m?)

L/s/person **5,50** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_vent_reclaim

05.18.2017

Prepared by:

09:06

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	577 m²	55421	-	577 m²	-	-
Wall Transmission	2073 m²	10790	-	2073 m²	14351	-
Roof Transmission	1155 m²	4285	-	1155 m²	5927	-
Window Transmission	577 m²	7495	-	577 m²	19278	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	145 m²	0	-	145 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	31749 W	26701	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	31749 W	29496	-	0	0	-
People	317	18270	19075	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	15246	1907	10%	3956	0
>> Total Zone Loads	-	167704	20982	-	43511	0
Zone Conditioning	-	162304	20982	-	44258	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Ventilation Load	1746 L/s	9693	3628	1746 L/s	26303	0
Ventilation Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	175231	24610	-	67327	0
Cooling Coil	-	26556	7785	-	0	0
Heating Coil	-	0	-	-	27436	-
Terminal Unit Cooling	-	148728	17307	-	0	0

Terminal Unit Heating	-	0	-	-	39891	-
>> Total Conditioning	-	175285	25091	-	67327	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	2133	2133	2133	494	n/a	n/a
April	16685	16685	16685	3884	n/a	n/a
May	44761	44761	44761	10486	n/a	n/a
June	73833	73833	73833	17638	n/a	n/a
July	93006	93006	93006	22618	n/a	n/a
August	95895	95895	95895	23364	n/a	n/a
September	60581	60581	60581	14440	n/a	n/a
October	30699	30699	30699	7164	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	417592	417592	417592	100088	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Mtatsminda_vent_reclaim

05.18.2017

Prepared by:

09:06

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	10481	0	5163
February	0	9956	0	7335
March	137	0	1996	6959
April	946	0	15739	0
May	3935	0	40826	0
June	11474	0	62358	0
July	22553	0	70453	0
August	26197	0	69698	0
September	10632	0	49949	0
October	3504	0	27195	128
November	0	3762	0	659
December	0	8389	0	4486
Total	79378	32588	338214	24730

Air System Information

Air System Name	As_build	Number of zones	5
Equipment Class	TERM	Floor Area	3174,9 m²
Air System Type	2P-FC	Location	Tbilisi, Georgia

Sizing Calculation Information

Calculation Months	Jan to Dec	Zone L/s Sizing	Sum of space airflow rates
Sizing Data	Calculated	Space L/s Sizing	Individual peak space loads

Cooling Coil Sizing Data

Total coil load	35,9 kW	Sensible heat ratio	0,753
Sensible coil load	27,0 kW	Water flow @ 6,0 K rise	1,43 L/s
Coil L/s at Jun 1500	1746 L/s		
Max coil L/s	1746 L/s		

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **15,2 / 14,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **27,6** kW
Coil L/s at Des Htg **1746** L/s
Max coil L/s **1746** L/s
Water flow @ 20,0 K drop **0,33** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,4 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1746** L/s
Standard L/s **1655** L/s
Actual max L/(s·m?) **0,55** L/(s·m?)

Fan motor BHP **2,04** BHP
Fan motor kW **1,62** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1746** L/s
L/(s·m?) **0,55** L/(s·m?)

L/s/person **5,50** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Chughureti_as_built

05.18.2017

Prepared by:

07:28

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	577 m²	88413	-	577 m²	-	-
Wall Transmission	2073 m²	16497	-	2073 m²	40959	-
Roof Transmission	1155 m²	15377	-	1155 m²	15362	-
Window Transmission	577 m²	18454	-	577 m²	47467	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	145 m²	0	-	145 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	31749 W	26701	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	31749 W	29496	-	0	0	-
People	317	18270	19075	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	21321	1907	10%	10379	0
>> Total Zone Loads	-	234530	20982	-	114167	0
Zone Conditioning	-	228669	20982	-	111967	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Ventilation Load	1746 L/s	9724	4825	1746 L/s	26118	0
Ventilation Fan Load	1746 L/s	1617	-	1746 L/s	-1617	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	241628	25807	-	134851	0
Cooling Coil	-	26525	7779	-	0	0
Heating Coil	-	0	-	-	27621	-
Terminal Unit Cooling	-	215103	18071	-	0	0

Terminal Unit Heating	-	0	-	-	107264	-
>> Total Conditioning	-	241628	25851	-	134885	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

დანართი 25: ჩულურეთის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	163	163	163	39	n/a	n/a
April	1286	1286	1286	302	n/a	n/a
May	5546	5546	5546	1304	n/a	n/a
June	10997	10997	10997	2637	n/a	n/a
July	14969	14969	14969	3647	n/a	n/a
August	15498	15498	15498	3780	n/a	n/a
September	9005	9005	9005	2154	n/a	n/a
October	3295	3295	3295	778	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	60760	60760	60760	14641	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Chughureti_as_built

05.18.2017

Prepared by:

07:28

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	4019	0	3181
February	0	3701	0	3694
March	11	0	152	5088
April	76	0	1210	0
May	353	0	5193	0
June	1241	0	9756	0
July	2670	0	12299	0
August	3231	0	12267	0
September	1036	0	7970	0
October	268	0	3027	255
November	0	1885	0	682
December	0	3221	0	2724
Total	8886	12825	51874	15624

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **2**
 Floor Area **406,2** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **6,2** kW
 Sensible coil load **5,7** kW
 Coil L/s at Jul 1500 **291** L/s
 Max coil L/s **291** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,25** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **9,0** kW
Coil L/s at Des Htg **291** L/s
Max coil L/s **291** L/s
Water flow @ 20,0 K drop **0,11** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **291** L/s
L/(s·m?) **0,72** L/(s·m?)

L/s/person **4,30** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_new_windows

05.18.2017

Prepared by:

07:34

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	72 m?	13265	-	72 m?	-	-
Wall Transmission	432 m?	5581	-	432 m?	15218	-
Roof Transmission	262 m?	3172	-	262 m?	3479	-
Window Transmission	72 m?	2329	-	72 m?	5990	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	145 m?	0	-	145 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	4062 W	3416	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	4062 W	3774	-	0	0	-
People	68	3896	4067	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	3543	407	10%	2469	0
>> Total Zone Loads	-	38975	4474	-	27155	0
Zone Conditioning	-	37780	4474	-	26138	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	291 L/s	270	-	291 L/s	-270	-
Ventilation Load	291 L/s	3241	806	291 L/s	8638	0
Ventilation Fan Load	291 L/s	270	-	291 L/s	-270	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	41560	5280	-	34236	0
Cooling Coil	-	5377	413	-	0	0
Heating Coil	-	0	-	-	8959	-
Terminal Unit Cooling	-	36183	4862	-	0	0

Terminal Unit Heating	-	0	-	-	25278	-
>> Total Conditioning	-	41560	5275	-	34236	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	115	115	115	27	n/a	n/a
April	947	947	947	223	n/a	n/a
May	4538	4538	4538	1067	n/a	n/a
June	9337	9337	9337	2239	n/a	n/a
July	12930	12930	12930	3150	n/a	n/a
August	13559	13559	13559	3307	n/a	n/a
September	7596	7596	7596	1817	n/a	n/a
October	2773	2773	2773	654	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	51796	51796	51796	12484	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_new_windows

05.18.2017

Prepared by:

07:34

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	4019	0	2422
February	0	3701	0	2956
March	11	0	104	4697
April	76	0	870	0
May	353	0	4185	0
June	1241	0	8096	0
July	2670	0	10260	0
August	3231	0	10328	0
September	1036	0	6561	0
October	268	0	2505	255
November	0	1885	0	466
December	0	3221	0	2045
Total	8886	12825	42910	12842

Air System Information

Air System Name **As_build**

Number of zones **2**

Equipment Class **TERM**

Floor Area **406,2** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **6,2** kW

Sensible heat ratio **0,923**

Sensible coil load **5,7** kW

Water flow @ 6,0 K rise **0,25** L/s

Coil L/s at Jul 1500 **291** L/s

Max coil L/s **291** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **9,0** kW
Coil L/s at Des Htg **291** L/s
Max coil L/s **291** L/s
Water flow @ 20,0 K drop **0,11** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **291** L/s
L/(s·m?) **0,72** L/(s·m?)

L/s/person **4,30** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_walls_insulation

05.18.2017

Prepared by:

07:37

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	72 m?	7393	-	72 m?	-	-
Wall Transmission	432 m?	5794	-	432 m?	15218	-
Roof Transmission	262 m?	3614	-	262 m?	3479	-
Window Transmission	72 m?	868	-	72 m?	2406	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	145 m?	0	-	145 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	4062 W	3459	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	4062 W	3793	-	0	0	-
People	68	3959	4067	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	2888	407	10%	2110	0
>> Total Zone Loads	-	31769	4474	-	23212	0
Zone Conditioning	-	30943	4474	-	22161	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	291 L/s	270	-	291 L/s	-270	-
Ventilation Load	291 L/s	2861	728	291 L/s	8625	0
Ventilation Fan Load	291 L/s	270	-	291 L/s	-270	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	34343	5202	-	30247	0
Cooling Coil	-	4985	341	-	0	0
Heating Coil	-	0	-	-	8959	-
Terminal Unit Cooling	-	29358	4860	-	0	0

Terminal Unit Heating	-	0	-	-	21288	-
>> Total Conditioning	-	34343	5201	-	30247	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	292	292	292	68	n/a	n/a
April	2069	2069	2069	481	n/a	n/a
May	6156	6156	6156	1443	n/a	n/a
June	10310	10310	10310	2471	n/a	n/a
July	13216	13216	13216	3229	n/a	n/a
August	13733	13733	13733	3360	n/a	n/a
September	8573	8573	8573	2048	n/a	n/a
October	4196	4196	4196	981	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	58546	58546	58546	14081	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_walls_insulation

05.18.2017

Prepared by:

07:37

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	4019	0	240
February	0	3701	0	551
March	11	0	281	2228
April	76	0	1992	0
May	353	0	5803	0
June	1241	0	9069	0
July	2670	0	10545	0
August	3231	0	10503	0
September	1036	0	7537	0
October	268	0	3929	115
November	0	1885	0	17
December	0	3221	0	229
Total	8886	12825	49660	3381

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **2**
 Floor Area **406,2** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **6,2** kW
 Sensible coil load **5,7** kW
 Coil L/s at Jul 1500 **291** L/s
 Max coil L/s **291** L/s
 Sensible heat ratio **0,923**

Water flow @ 6,0 K rise **0,25** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **9,0** kW
Coil L/s at Des Htg **291** L/s
Max coil L/s **291** L/s
Water flow @ 20,0 K drop **0,11** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **291** L/s
L/(s·m?) **0,72** L/(s·m?)

L/s/person **4,30** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_walls&roof_insulation

05.18.2017

Prepared by:

07:39

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	72 m?	13265	-	72 m?	-	-
Wall Transmission	432 m?	1151	-	432 m?	2995	-
Roof Transmission	262 m?	3172	-	262 m?	3479	-
Window Transmission	72 m?	2329	-	72 m?	5990	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	145 m?	0	-	145 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	4062 W	3416	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	4062 W	3774	-	0	0	-
People	68	3896	4067	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	3100	407	10%	1246	0
>> Total Zone Loads	-	34103	4474	-	13709	0
Zone Conditioning	-	33014	4474	-	13789	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	291 L/s	270	-	291 L/s	-270	-
Ventilation Load	291 L/s	3232	696	291 L/s	8766	0
Ventilation Fan Load	291 L/s	270	-	291 L/s	-270	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	36785	5170	-	22016	0
Cooling Coil	-	5377	413	-	0	0
Heating Coil	-	0	-	-	8959	-
Terminal Unit Cooling	-	31408	4756	-	0	0

Terminal Unit Heating	-	0	-	-	13066	-
>> Total Conditioning	-	36785	5169	-	22024	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	302	302	302	70	n/a	n/a
April	2114	2114	2114	491	n/a	n/a
May	5983	5983	5983	1402	n/a	n/a
June	9763	9763	9763	2340	n/a	n/a
July	12460	12460	12460	3045	n/a	n/a
August	13071	13071	13071	3199	n/a	n/a
September	8297	8297	8297	1982	n/a	n/a
October	4322	4322	4322	1009	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	56312	56312	56312	13539	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_walls&roof_insulation

05.18.2017

Prepared by:

07:39

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	4019	0	29
February	0	3701	0	144
March	11	0	291	1742
April	76	0	2037	0
May	353	0	5630	0
June	1241	0	8522	0
July	2670	0	9790	0
August	3231	0	9840	0
September	1036	0	7262	0
October	268	0	4055	84
November	0	1885	0	1
December	0	3221	0	17
Total	8886	12825	47426	2018

Air System Information

Air System Name **As_build**

Number of zones **2**

Equipment Class **TERM**

Floor Area **406,2** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **6,2** kW

Sensible heat ratio **0,923**

Sensible coil load **5,7** kW

Water flow @ 6,0 K rise **0,25** L/s

Coil L/s at Jul 1500 **291** L/s

Max coil L/s **291** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **9,0** kW
Coil L/s at Des Htg **291** L/s
Max coil L/s **291** L/s
Water flow @ 20,0 K drop **0,11** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **291** L/s
L/(s·m?) **0,72** L/(s·m?)

L/s/person **4,30** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_rebuild

05.18.2017

Prepared by:

07:41

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,0 °C / 20,7 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	72 m²	13767	-	72 m²	-	-
Wall Transmission	432 m²	948	-	432 m²	2995	-
Roof Transmission	262 m²	733	-	262 m²	1342	-
Window Transmission	72 m²	2013	-	72 m²	5990	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	145 m²	0	-	145 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	4062 W	3416	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	4062 W	3774	-	0	0	-
People	68	3896	4067	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	2855	407	10%	1033	0
>> Total Zone Loads	-	31403	4474	-	11359	0
Zone Conditioning	-	30881	4474	-	11026	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	291 L/s	270	-	291 L/s	-270	-
Ventilation Load	291 L/s	2821	264	291 L/s	8745	0
Ventilation Fan Load	291 L/s	270	-	291 L/s	-270	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	34241	4738	-	19232	0
Cooling Coil	-	4926	0	-	0	0
Heating Coil	-	0	-	-	8959	-
Terminal Unit Cooling	-	29315	4743	-	0	0

Terminal Unit Heating	-	0	-	-	10273	-
>> Total Conditioning	-	34241	4743	-	19232	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	361	361	361	85	n/a	n/a
April	2426	2426	2422	574	n/a	n/a
May	5461	5461	5459	1288	n/a	n/a
June	8159	8159	8159	1955	n/a	n/a
July	10231	10231	10231	2500	n/a	n/a
August	10911	10911	10911	2674	n/a	n/a
September	6895	6895	6895	1645	n/a	n/a
October	4216	4216	4216	982	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	48659	48659	48654	11702	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_rebuild

05.18.2017

Prepared by:

07:41

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	1138	0	0
February	0	1198	0	1
March	11	0	350	92
April	75	0	2350	0
May	339	0	5122	0
June	1151	0	7008	0
July	2442	0	7790	0
August	2975	0	7936	0
September	978	0	5917	0
October	267	0	3950	6
November	0	272	0	0
December	0	875	0	0
Total	8237	3484	40423	99

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **2**
 Floor Area **406,2** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **4,1** kW
 Sensible coil load **3,8** kW
 Coil L/s at Jun 1500 **291** L/s
 Max coil L/s **291** L/s

Sensible heat ratio **0,929**
 Water flow @ 6,0 K rise **0,16** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **4,6** kW
Coil L/s at Des Htg **291** L/s
Max coil L/s **291** L/s
Water flow @ 20,0 K drop **0,06** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,4 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **291** L/s
L/(s·m?) **0,72** L/(s·m?)

L/s/person **4,30** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_vent_reclaim

05.18.2017

Prepared by:

07:32

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	72 m²	8229	-	72 m²	-	-
Wall Transmission	432 m²	1151	-	432 m²	2995	-
Roof Transmission	262 m²	970	-	262 m²	1342	-
Window Transmission	72 m²	935	-	72 m²	2406	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	145 m²	0	-	145 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	4062 W	3416	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	4062 W	3774	-	0	0	-
People	68	3896	4067	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	2237	407	10%	674	0
>> Total Zone Loads	-	24609	4474	-	7417	0
Zone Conditioning	-	23518	4474	-	6971	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	291 L/s	270	-	291 L/s	-270	-
Ventilation Load	291 L/s	1613	427	291 L/s	4360	0
Ventilation Fan Load	291 L/s	270	-	291 L/s	-270	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	25670	4901	-	10791	0
Cooling Coil	-	3764	111	-	0	0
Heating Coil	-	0	-	-	4599	-
Terminal Unit Cooling	-	21896	4796	-	0	0

Terminal Unit Heating	-	0	-	-	6192	-
>> Total Conditioning	-	25661	4907	-	10791	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	178	178	178	42	n/a	n/a
April	1516	1516	1516	354	n/a	n/a
May	5822	5822	5822	1366	n/a	n/a
June	10974	10974	10974	2629	n/a	n/a
July	14750	14750	14750	3590	n/a	n/a
August	15279	15279	15279	3724	n/a	n/a
September	8985	8985	8985	2147	n/a	n/a
October	3484	3484	3484	820	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	60988	60988	60988	14673	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Chughureti_vent_reclaim

05.18.2017

Prepared by:

07:32

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	2045	0	3179
February	0	1867	0	3680
March	11	0	167	3366
April	75	0	1441	0
May	338	0	5483	0
June	1151	0	9823	0
July	2441	0	12309	0
August	2973	0	12306	0
September	976	0	8009	0
October	266	0	3217	79
November	0	896	0	652
December	0	1645	0	2703
Total	8232	6453	52756	13658

Air System Information

Air System Name **As_build** Number of zones **2**
 Equipment Class **TERM** Floor Area **406,2** m²
 Air System Type **2P-FC** Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec** Zone L/s Sizing **Sum of space airflow rates**
 Sizing Data **Calculated** Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **4,1** kW Water flow @ 6,0 K rise **0,16** L/s
 Sensible coil load **3,8** kW
 Coil L/s at Jun 1500 **291** L/s
 Max coil L/s **291** L/s
 Sensible heat ratio **0,929**

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **4,6** kW
Coil L/s at Des Htg **291** L/s
Max coil L/s **291** L/s
Water flow @ 20,0 K drop **0,06** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,3 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **291** L/s
Standard L/s **276** L/s
Actual max L/(s·m?) **0,72** L/(s·m?)

Fan motor BHP **0,34** BHP
Fan motor kW **0,27** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **291** L/s
L/(s·m?) **0,72** L/(s·m?)

L/s/person **4,30** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Isani_as_built

05.18.2017

Prepared by:

01:16

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 33,3 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	72 m²	13265	-	72 m²	-	-
Wall Transmission	432 m²	5581	-	432 m²	15218	-
Roof Transmission	262 m²	3172	-	262 m²	3479	-
Window Transmission	72 m²	2329	-	72 m²	5990	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	145 m²	0	-	145 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	4062 W	3416	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	4062 W	3774	-	0	0	-
People	68	3896	4067	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	3543	407	10%	2469	0
>> Total Zone Loads	-	38975	4474	-	27155	0
Zone Conditioning	-	37780	4474	-	26138	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	291 L/s	270	-	291 L/s	-270	-
Ventilation Load	291 L/s	1621	804	291 L/s	4319	0
Ventilation Fan Load	291 L/s	270	-	291 L/s	-270	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	39940	5278	-	29917	0
Cooling Coil	-	3756	110	-	0	0
Heating Coil	-	0	-	-	4640	-
Terminal Unit Cooling	-	36183	5163	-	0	0

Terminal Unit Heating	-	0	-	-	25278	-
>> Total Conditioning	-	39939	5273	-	29917	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

დანართი 26: ისანის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1364	1364	1364	316	n/a	n/a
April	9806	9806	9806	2278	n/a	n/a
May	27213	27213	27213	6365	n/a	n/a
June	45273	45273	45273	10797	n/a	n/a
July	53532	53532	53532	13035	n/a	n/a
August	52972	52972	52972	12922	n/a	n/a
September	34456	34456	34456	8213	n/a	n/a
October	16583	16583	16583	3875	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	241197	241197	241197	57802	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Isani_as_build

05.18.2017

Prepared by:

01:16

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	7346
February	0	8294	0	7711
March	24	0	1339	6676
April	171	0	9634	0
May	791	0	26421	0
June	2782	0	42491	0
July	5985	0	47547	0
August	7241	0	45730	0
September	2321	0	32135	0
October	600	0	15983	334
November	0	4224	0	1456
December	0	7218	0	6438
Total	19917	28745	221281	29961

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW
 Sensible coil load **12,8** kW
 Coil L/s at Jul 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,56** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_new_windows

05.18.2017

Prepared by:

01:19

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m²	70664	-	571 m²	-	-
Wall Transmission	290 m²	3328	-	290 m²	10219	-
Roof Transmission	500 m²	7016	-	500 m²	6651	-
Window Transmission	571 m²	16122	-	571 m²	47502	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	12698	597	10%	6437	0
>> Total Zone Loads	-	139683	6567	-	70810	0
Zone Conditioning	-	135670	6567	-	69787	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	5930	2403	652 L/s	19752	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	142809	8970	-	88331	0
Cooling Coil	-	10757	1065	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	132052	8150	-	0	0

Terminal Unit Heating	-	0	-	-	68240	-
>> Total Conditioning	-	142809	9215	-	88320	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1197	1197	1197	278	n/a	n/a
April	8340	8340	8340	1944	n/a	n/a
May	21294	21294	21294	4986	n/a	n/a
June	33904	33904	33904	8087	n/a	n/a
July	39931	39931	39931	9723	n/a	n/a
August	40224	40224	40224	9816	n/a	n/a
September	26283	26283	26283	6263	n/a	n/a
October	14032	14032	14032	3272	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	185205	185205	185205	44368	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_new_windows

05.18.2017

Prepared by:

01:19

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	1492
February	0	8294	0	2177
March	24	0	1173	3210
April	171	0	8168	0
May	791	0	20503	0
June	2782	0	31121	0
July	5985	0	33946	0
August	7241	0	32983	0
September	2321	0	23962	0
October	600	0	13432	151
November	0	4224	0	138
December	0	7218	0	1320
Total	19917	28745	165288	8488

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW
 Sensible coil load **12,8** kW
 Coil L/s at Jul 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,56** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_walls_insulation

05.18.2017

Prepared by:

01:22

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m²	43837	-	571 m²	-	-
Wall Transmission	290 m²	3328	-	290 m²	10219	-
Roof Transmission	500 m²	7016	-	500 m²	6651	-
Window Transmission	571 m²	6475	-	571 m²	19077	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	9051	597	10%	3595	0
>> Total Zone Loads	-	99561	6567	-	39543	0
Zone Conditioning	-	97565	6567	-	39439	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	6004	2503	652 L/s	19803	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	104777	9070	-	58034	0
Cooling Coil	-	10757	1065	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	94020	8112	-	0	0

Terminal Unit Heating	-	0	-	-	37961	-
>> Total Conditioning	-	104777	9177	-	58040	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1462	1462	1462	339	n/a	n/a
April	10435	10435	10435	2427	n/a	n/a
May	27695	27695	27695	6479	n/a	n/a
June	44870	44870	44870	10701	n/a	n/a
July	52396	52396	52396	12767	n/a	n/a
August	51722	51722	51722	12627	n/a	n/a
September	33988	33988	33988	8102	n/a	n/a
October	17098	17098	17098	3992	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	239666	239666	239666	57434	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_walls_insulation

05.18.2017

Prepared by:

01:22

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	5105
February	0	8294	0	5601
March	24	0	1437	5019
April	171	0	10264	0
May	791	0	26904	0
June	2782	0	42087	0
July	5985	0	46412	0
August	7241	0	44481	0
September	2321	0	31667	0
October	600	0	16498	261
November	0	4224	0	862
December	0	7218	0	4508
Total	19917	28745	219750	21356

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW
 Sensible coil load **12,8** kW
 Coil L/s at Jul 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **0,56** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_walls&roof_insulation

05.18.2017

Prepared by:

01:25

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m?	67858	-	571 m?	-	-
Wall Transmission	290 m?	746	-	290 m?	2011	-
Roof Transmission	500 m?	6911	-	500 m?	6651	-
Window Transmission	571 m?	17149	-	571 m?	47502	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	772 m?	0	-	772 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	12252	597	10%	5616	0
>> Total Zone Loads	-	134769	6567	-	61781	0
Zone Conditioning	-	133006	6567	-	62010	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	6429	2122	652 L/s	19807	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	140644	8688	-	80609	0
Cooling Coil	-	11172	763	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	129471	7985	-	0	0

Terminal Unit Heating	-	0	-	-	60525	-
>> Total Conditioning	-	140644	8749	-	80604	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1495	1495	1495	347	n/a	n/a
April	10510	10510	10510	2447	n/a	n/a
May	27351	27351	27351	6401	n/a	n/a
June	43823	43823	43823	10451	n/a	n/a
July	50968	50968	50968	12419	n/a	n/a
August	50449	50449	50449	12320	n/a	n/a
September	33436	33436	33436	7968	n/a	n/a
October	17321	17321	17321	4041	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	235353	235353	235353	56394	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_walls&roof_insulation

05.18.2017

Prepared by:

01:25

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	9008	0	3767
February	0	8294	0	4465
March	24	0	1470	4212
April	171	0	10339	0
May	791	0	26560	0
June	2782	0	41041	0
July	5985	0	44983	0
August	7241	0	43207	0
September	2321	0	31115	0
October	600	0	16721	220
November	0	4224	0	478
December	0	7218	0	3306
Total	19917	28745	215437	16448

Air System Information

Air System Name **As_build**

Number of zones **3**

Equipment Class **TERM**

Floor Area **1346,8** m²

Air System Type **2P-FC**

Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**

Zone L/s Sizing **Sum of space airflow rates**

Sizing Data **Calculated**

Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **13,9** kW

Sensible heat ratio **0,923**

Sensible coil load **12,8** kW

Water flow @ 6,0 K rise **0,56** L/s

Coil L/s at Jul 1500 **652** L/s

Max coil L/s **652** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **20,1** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,24** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_rebuild

05.18.2017

Prepared by:

02:39

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m?	67858	-	571 m?	-	-
Wall Transmission	290 m?	746	-	290 m?	2011	-
Roof Transmission	500 m?	2194	-	500 m?	2566	-
Window Transmission	571 m?	17149	-	571 m?	47502	-
Skylight Transmission	0 m?	0	-	0 m?	0	-
Door Loads	0 m?	0	-	0 m?	0	-
Floor Transmission	772 m?	0	-	772 m?	0	-
Partitions	0 m?	0	-	0 m?	0	-
Ceiling	0 m?	0	-	0 m?	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	11780	597	10%	5208	0
>> Total Zone Loads	-	129581	6567	-	57287	0
Zone Conditioning	-	127533	6567	-	57068	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	6419	2076	652 L/s	19797	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	135161	8643	-	75657	0
Cooling Coil	-	11172	763	-	0	0
Heating Coil	-	0	-	-	20079	-
Terminal Unit Cooling	-	123989	7933	-	0	0

Terminal Unit Heating	-	0	-	-	55600	-
>> Total Conditioning	-	135161	8696	-	75679	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1865	1865	1801	440	n/a	n/a
April	11238	11238	10857	2633	n/a	n/a
May	22767	22767	22633	5355	n/a	n/a
June	32608	32608	32592	7785	n/a	n/a
July	36907	36907	36907	8994	n/a	n/a
August	37218	37218	37218	9095	n/a	n/a
September	25248	25248	25248	6010	n/a	n/a
October	15929	15929	15929	3711	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	183780	183780	183184	44024	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Isani_rebuild

05.18.2017

Prepared by:

02:39

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	1966	0	59
February	0	1932	0	175
March	24	0	1840	16
April	170	0	11068	0
May	761	0	22006	0
June	2585	0	30023	0
July	5480	0	31427	0
August	6671	0	30547	0
September	2193	0	23055	0
October	598	0	15331	2
November	0	279	0	0
December	0	1291	0	43
Total	18484	5468	165297	295

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **1346,8** m²
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **9,3** kW
 Sensible coil load **8,6** kW
 Coil L/s at Jun 1500 **652** L/s
 Max coil L/s **652** L/s

Sensible heat ratio **0,928**
 Water flow @ 6,0 K rise **0,37** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,8 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **10,2** kW
Coil L/s at Des Htg **652** L/s
Max coil L/s **652** L/s
Water flow @ 20,0 K drop **0,12** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,6 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **652** L/s
Standard L/s **619** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **0,76** BHP
Fan motor kW **0,60** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **652** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,57** L/s/person

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m²	43837	-	571 m²	-	-
Wall Transmission	290 m²	689	-	290 m²	2011	-
Roof Transmission	500 m²	2232	-	500 m²	2566	-
Window Transmission	571 m²	6475	-	571 m²	19077	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	8309	597	10%	2365	0
>> Total Zone Loads	-	91395	6567	-	26020	0
Zone Conditioning	-	89550	6567	-	26420	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	2992	2450	652 L/s	9927	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	93750	9016	-	35138	0
Cooling Coil	-	7765	500	-	0	0
Heating Coil	-	0	-	-	10153	-
Terminal Unit Cooling	-	85985	8547	-	0	0
Terminal Unit Heating	-	0	-	-	24992	-

>> Total Conditioning	-	93750	9048	-	35145	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1581	1581	1581	367	n/a	n/a
April	10939	10939	10939	2546	n/a	n/a
May	28094	28094	28094	6572	n/a	n/a
June	45309	45309	45309	10800	n/a	n/a
July	53069	53069	53069	12916	n/a	n/a
August	52464	52464	52464	12794	n/a	n/a
September	34427	34427	34427	8202	n/a	n/a
October	17265	17265	17265	4030	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	243149	243149	243149	58227	n/a	n/a

Air System Simulation Results (Table 1) :

Heating Coil Sizing Data

Max coil load	10,2 kW	Load occurs at	Des Htg
Coil L/s at Des Htg	652 L/s	Ent. DB / Lvg DB	7,5 / 21,2 °C
Max coil L/s	652 L/s		
Water flow @ 20,0 K drop	0,12 L/s		

Ventilation Fan Sizing Data

Actual max L/s	652 L/s	Fan motor BHP	0,76 BHP
Standard L/s	619 L/s	Fan motor kW	0,60 kW
Actual max L/(s·m?)	0,48 L/(s·m?)	Fan static	500 Pa

Exhaust Fan Sizing Data

Actual max L/s	652 L/s	Fan motor BHP	0,76 BHP
Standard L/s	619 L/s	Fan motor kW	0,60 kW
Actual max L/(s·m?)	0,48 L/(s·m?)	Fan static	500 Pa

Outdoor Ventilation Air Data

Design airflow L/s	652 L/s	L/s/person	6,57 L/s/person
L/(s·m?)	0,48 L/(s·m?)		

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_as_built

05.22.2017

Prepared by:

11:35

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	571 m²	70664	-	571 m²	-	-
Wall Transmission	290 m²	3328	-	290 m²	10219	-
Roof Transmission	500 m²	7016	-	500 m²	6651	-
Window Transmission	571 m²	16122	-	571 m²	47502	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	13468 W	11467	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	13468 W	12575	-	0	0	-
People	99	5811	5970	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	12698	597	10%	6437	0
>> Total Zone Loads	-	139683	6567	-	70810	0
Zone Conditioning	-	135670	6567	-	69787	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	652 L/s	604	-	652 L/s	-604	-
Ventilation Load	652 L/s	2965	2399	652 L/s	9876	0
Ventilation Fan Load	652 L/s	604	-	652 L/s	-604	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	139844	8966	-	78455	0
Cooling Coil	-	7792	505	-	0	0
Heating Coil	-	0	-	-	10203	-
Terminal Unit Cooling	-	132052	8708	-	0	0

Terminal Unit Heating	-	0	-	-	68240	-
>> Total Conditioning	-	139844	9213	-	78443	0

დანართი 27: სამგორის რაიონის გამგეობის შენობის ენერგოკომპონენტების სიმულაციური ანალიზის მონაცემები

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1775	1775	1775	411	n/a	n/a
April	11652	11652	11652	2707	n/a	n/a
May	33336	33336	33336	7815	n/a	n/a
June	58443	58443	58443	13986	n/a	n/a
July	74547	74547	74547	18180	n/a	n/a
August	77648	77648	77648	18968	n/a	n/a
September	46757	46757	46757	11163	n/a	n/a
October	23627	23627	23627	5515	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	327784	327784	327784	78745	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_as_built

05.22.2017

Prepared by:

11:35

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	23709	0	10826
February	0	21830	0	11442
March	64	0	1711	16080
April	450	0	11201	0
May	2083	0	31253	0
June	7323	0	51120	0
July	15751	0	58795	0
August	19058	0	58590	0
September	6110	0	40647	0
October	1579	0	22048	948
November	0	11118	0	2946
December	0	18997	0	9133
Total	52418	75654	275367	51375

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **3592,0** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **36,6** kW
 Sensible coil load **33,8** kW
 Coil L/s at Jul 1500 **1717** L/s
 Max coil L/s **1717** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **1,46** L/s

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **52,8** kW
Coil L/s at Des Htg **1717** L/s
Max coil L/s **1717** L/s
Water flow @ 20,0 K drop **0,63** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1717** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,71** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_new_windows

05.22.2017

Prepared by:

11:37

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,8 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	50202	-	330 m²	-	-
Wall Transmission	1184 m²	15020	-	1184 m²	41715	-
Roof Transmission	1305 m²	17660	-	1305 m²	17360	-
Window Transmission	330 m²	10080	-	330 m²	27453	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	35920 W	30209	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	35920 W	33372	-	0	0	-
People	256	14722	15370	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	17126	1537	10%	8653	0
>> Total Zone Loads	-	188391	16907	-	95181	0
Zone Conditioning	-	180423	16907	-	94248	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Ventilation Load	1717 L/s	18016	4974	1717 L/s	51963	0
Ventilation Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	201619	21881	-	143031	0
Cooling Coil	-	30625	3232	-	0	0
Heating Coil	-	0	-	-	52846	-
Terminal Unit Cooling	-	170994	18743	-	0	0

Terminal Unit Heating	-	0	-	-	90261	-
>> Total Conditioning	-	201619	21975	-	143107	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	1624	1624	1624	376	n/a	n/a
April	10392	10392	10392	2413	n/a	n/a
May	29098	29098	29098	6822	n/a	n/a
June	51041	51041	51041	12218	n/a	n/a
July	65720	65720	65720	16032	n/a	n/a
August	69375	69375	69375	16957	n/a	n/a
September	41209	41209	41209	9837	n/a	n/a
October	21731	21731	21731	5068	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	290190	290190	290190	69722	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **52,8** kW
Coil L/s at Des Htg **1717** L/s
Max coil L/s **1717** L/s
Water flow @ 20,0 K drop **0,63** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1717** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,71** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_walls_insulation

05.22.2017

Prepared by:

11:40

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	30601	-	330 m²	-	-
Wall Transmission	1184 m²	15843	-	1184 m²	41715	-
Roof Transmission	1305 m²	18038	-	1305 m²	17360	-
Window Transmission	330 m²	3980	-	330 m²	11025	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	35920 W	30585	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	35920 W	33539	-	0	0	-
People	256	14962	15370	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	14755	1537	10%	7010	0
>> Total Zone Loads	-	162301	16907	-	77111	0
Zone Conditioning	-	156425	16907	-	77920	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Ventilation Load	1717 L/s	16791	4314	1717 L/s	52099	0
Ventilation Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	176395	21222	-	126839	0
Cooling Coil	-	29404	2009	-	0	0
Heating Coil	-	0	-	-	52846	-
Terminal Unit Cooling	-	146992	19319	-	0	0

Terminal Unit Heating	-	0	-	-	74014	-
>> Total Conditioning	-	176395	21328	-	126860	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	2215	2215	2215	514	n/a	n/a
April	14073	14073	14073	3276	n/a	n/a
May	35051	35051	35051	8217	n/a	n/a
June	56581	56581	56581	13540	n/a	n/a
July	69811	69811	69811	17055	n/a	n/a
August	72844	72844	72844	17830	n/a	n/a
September	45486	45486	45486	10857	n/a	n/a
October	26077	26077	26077	6078	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	322139	322139	322139	77368	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jul 1500**
OA DB / WB **34,4 / 21,8** °C
Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **52,8** kW
Coil L/s at Des Htg **1717** L/s
Max coil L/s **1717** L/s
Water flow @ 20,0 K drop **0,63** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1717** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,71** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Samgori_walls&roof_insulation

05.22.2017

Prepared by:

11:46

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	49328	-	330 m²	-	-
Wall Transmission	1184 m²	3243	-	1184 m²	8209	-
Roof Transmission	1305 m²	18038	-	1305 m²	17360	-
Window Transmission	330 m²	9911	-	330 m²	27453	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	35920 W	30585	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	35920 W	33539	-	0	0	-
People	256	14962	15370	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	15960	1537	10%	5302	0
>> Total Zone Loads	-	175565	16907	-	58324	0
Zone Conditioning	-	170245	16907	-	57220	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Ventilation Load	1717 L/s	16817	4578	1717 L/s	52162	0
Ventilation Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	190242	21486	-	106201	0
Cooling Coil	-	29404	2009	-	0	0
Heating Coil	-	0	-	-	52846	-
Terminal Unit Cooling	-	160839	19582	-	0	0

Terminal Unit Heating	-	0	-	-	53377	-
>> Total Conditioning	-	190242	21590	-	106223	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	2268	2268	2268	527	n/a	n/a
April	14287	14287	14287	3337	n/a	n/a
May	34080	34080	34080	8001	n/a	n/a
June	53808	53808	53808	12879	n/a	n/a
July	66058	66058	66058	16144	n/a	n/a
August	69547	69547	69547	17043	n/a	n/a
September	44046	44046	44046	10510	n/a	n/a
October	26618	26618	26618	6201	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	310711	310711	310711	74642	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary for As_build

Project Name: Samgori_walls&roof_insulation

05.22.2017

Prepared by:

11:46

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	23709	0	264
February	0	21830	0	832
March	64	0	2203	5560
April	450	0	13836	0
May	2083	0	31997	0
June	7323	0	46485	0
July	15751	0	50307	0
August	19058	0	50489	0
September	6110	0	37936	0
October	1579	0	25040	522
November	0	11118	0	3
December	0	18997	0	134
Total	52418	75654	258294	7315

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **3592,0** m?
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **36,6** kW
 Sensible coil load **33,8** kW
 Coil L/s at Jul 1500 **1717** L/s
 Max coil L/s **1717** L/s

Sensible heat ratio **0,923**
 Water flow @ 6,0 K rise **1,46** L/s

Load occurs at **Jul 1500**
 OA DB / WB **34,4 / 21,8** °C
 Entering DB / WB **34,4 / 21,8** °C

Leaving DB / WB **17,2 / 16,0** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **52,8** kW
 Coil L/s at Des Htg **1717** L/s
 Max coil L/s **1717** L/s
 Water flow @ 20,0 K drop **0,63** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **-5,7 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1717** L/s
 Standard L/s **1628** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
 Fan motor kW **1,59** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1717** L/s
 Standard L/s **1628** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
 Fan motor kW **1,59** kW
 Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1717** L/s
 L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,71** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_rebuild

05.22.2017

Prepared by:

11:48

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	49589	-	330 m²	-	-
Wall Transmission	1184 m²	3101	-	1184 m²	8209	-
Roof Transmission	1305 m²	5826	-	1305 m²	6698	-
Window Transmission	330 m²	9317	-	330 m²	27453	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	35920 W	30585	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	35920 W	33539	-	0	0	-
People	256	14962	15370	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	14692	1537	10%	4236	0
>> Total Zone Loads	-	161611	16907	-	46596	0
Zone Conditioning	-	155641	16907	-	43730	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Ventilation Load	1717 L/s	15719	5016	1717 L/s	52066	0
Ventilation Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	174540	21923	-	92615	0
Cooling Coil	-	28312	2802	-	0	0
Heating Coil	-	0	-	-	52846	-
Terminal Unit Cooling	-	146201	19463	-	0	0

Terminal Unit Heating	-	0	-	-	39791	-
>> Total Conditioning	-	174513	22266	-	92637	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	3569	3569	3339	836	n/a	n/a
April	18531	18531	17662	4307	n/a	n/a
May	32943	32943	32740	7755	n/a	n/a
June	46699	46699	46697	11202	n/a	n/a
July	56027	56027	56027	13700	n/a	n/a
August	59990	59990	59990	14728	n/a	n/a
September	38454	38454	38454	9166	n/a	n/a
October	27314	27314	27314	6367	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	283528	283528	282224	68060	n/a	n/a

Air System Simulation Results (Table 1) :

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_rebuild

05.22.2017

Prepared by:

11:48

Month	Precool Coil Load (kWh)	Preheat Coil Load (kWh)	Terminal Cooling Coil Load (kWh)	Terminal Heating Coil Load (kWh)
January	0	2679	0	10
February	0	3148	0	98
March	64	0	3505	38
April	449	0	18082	0
May	2003	0	30940	0
June	6798	0	39902	0
July	14412	0	41615	0
August	17551	0	42439	0
September	5771	0	32683	0
October	1574	0	25741	29
November	0	161	0	0
December	0	1196	0	4
Total	48622	7184	234906	179

Air System Information

Air System Name **As_build**
 Equipment Class **TERM**
 Air System Type **2P-FC**

Number of zones **3**
 Floor Area **3592,0** m²
 Location **Tbilisi, Georgia**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Cooling Coil Sizing Data

Total coil load **24,3** kW
 Sensible coil load **22,6** kW
 Coil L/s at Jun 1500 **1717** L/s
 Max coil L/s **1717** L/s

Sensible heat ratio **0,929**
 Water flow @ 6,0 K rise **0,97** L/s

Load occurs at **Jun 1500**
OA DB / WB **33,8 / 21,8** °C
Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **26,7** kW
Coil L/s at Des Htg **1717** L/s
Max coil L/s **1717** L/s
Water flow @ 20,0 K drop **0,32** L/s

Load occurs at **Des Htg**
Ent. DB / Lvg DB **7,6 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1717** L/s
Standard L/s **1628** L/s
Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
Fan motor kW **1,59** kW
Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1717** L/s
L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,71** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_vent_reclaim

05.22.2017

Prepared by:

11:51

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,6 °C / 21,2 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	30763	-	330 m²	-	-
Wall Transmission	1184 m²	3101	-	1184 m²	8209	-
Roof Transmission	1305 m²	5826	-	1305 m²	6698	-
Window Transmission	330 m²	3742	-	330 m²	11025	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	35920 W	30585	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	35920 W	33539	-	0	0	-
People	256	14962	15370	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	12252	1537	10%	2593	0
>> Total Zone Loads	-	134769	16907	-	28525	0
Zone Conditioning	-	130299	16907	-	29355	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Ventilation Load	1717 L/s	7861	5310	1717 L/s	26167	0
Ventilation Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	141340	22218	-	52342	0
Cooling Coil	-	20451	1319	-	0	0
Heating Coil	-	0	-	-	26679	-
Terminal Unit Cooling	-	120889	20926	-	0	0

Terminal Unit Heating	-	0	-	-	25725	-
>> Total Conditioning	-	141340	22246	-	52404	0
Key:	Positive values are clg loads			Positive values are htg loads		
	Negative values are htg loads			Negative values are clg loads		

Plant Simulation Results (Table 1) :

Month	Cooling Coil Load (kWh)	Plant Cooling Load (kWh)	Chiller Output (kWh)	Chiller Input (kWh)	Primary Water Dist. Pump (kWh)	Secondary Water Dist. Pump (kWh)
January	0	0	0	0	n/a	n/a
February	0	0	0	0	n/a	n/a
March	2472	2472	2472	574	n/a	n/a
April	15212	15212	15212	3546	n/a	n/a
May	35818	35818	35818	8391	n/a	n/a
June	58534	58534	58534	13993	n/a	n/a
July	73287	73287	73287	17856	n/a	n/a
August	76322	76322	76322	18635	n/a	n/a
September	46707	46707	46707	11143	n/a	n/a
October	25559	25559	25559	5957	n/a	n/a
November	0	0	0	0	n/a	n/a
December	0	0	0	0	n/a	n/a
Total	333910	333910	333910	80096	n/a	n/a

Air System Simulation Results (Table 1) :

Load occurs at **Jun 1500**
 OA DB / WB **33,8 / 21,8** °C
 Entering DB / WB **28,7 / 20,3** °C

Leaving DB / WB **17,2 / 16,4** °C
 Bypass Factor **0,100**

Heating Coil Sizing Data

Max coil load **26,9** kW
 Coil L/s at Des Htg **1717** L/s
 Max coil L/s **1717** L/s
 Water flow @ 20,0 K drop **0,32** L/s

Load occurs at **Des Htg**
 Ent. DB / Lvg DB **7,5 / 21,2** °C

Ventilation Fan Sizing Data

Actual max L/s **1717** L/s
 Standard L/s **1628** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
 Fan motor kW **1,59** kW
 Fan static **500** Pa

Exhaust Fan Sizing Data

Actual max L/s **1717** L/s
 Standard L/s **1628** L/s
 Actual max L/(s·m?) **0,48** L/(s·m?)

Fan motor BHP **2,00** BHP
 Fan motor kW **1,59** kW
 Fan static **500** Pa

Outdoor Ventilation Air Data

Design airflow L/s **1717** L/s
 L/(s·m?) **0,48** L/(s·m?)

L/s/person **6,71** L/s/person

Dedicated Outdoor Air System (DOAS) Sizing Summary

Project Name: Samgori_vent_reclaim

05.22.2017

Prepared by:

11:51

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,8 °C / 21,5 °C			HEATING OA DB / WB -5,7 °C / -7,0 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	330 m²	50202	-	330 m²	-	-
Wall Transmission	1184 m²	15020	-	1184 m²	41715	-
Roof Transmission	1305 m²	17660	-	1305 m²	17360	-
Window Transmission	330 m²	10080	-	330 m²	27453	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	772 m²	0	-	772 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	35920 W	30209	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	35920 W	33372	-	0	0	-
People	256	14722	15370	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	10% / 10%	17126	1537	10%	8653	0
>> Total Zone Loads	-	188391	16907	-	95181	0
Zone Conditioning	-	180423	16907	-	94248	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Exhaust Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Ventilation Load	1717 L/s	9008	4955	1717 L/s	25982	0
Ventilation Fan Load	1717 L/s	1590	-	1717 L/s	-1590	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	192611	21863	-	117050	0
Cooling Coil	-	21617	1542	-	0	0
Heating Coil	-	0	-	-	26864	-
Terminal Unit Cooling	-	170994	20414	-	0	0

Terminal Unit Heating	-	0	-	-	90261	-
>> Total Conditioning	-	192611	21956	-	117125	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

